Exterior Foam Net Zero Assembly

See *Appendix A: Exterior Foam Net Zero Assembly Construction Details* for plans and construction details.

Description & Overview

This assembly followed the same principles as the Exterior Mineral Wool Tier 3 Assembly in that it is a structural 2x6 wall with insulation to the exterior of structural sheathing and incorporates an airtight WRB. The difference being that this wall assembly utilized 6" of vapour closed XPS. This meant a VB membrane did not need to be installed interior of the structural framing. The XPS extends from the underside of the truss top chord overhang, down the face of the above grade walls, and down the face of the foundation as well. The wall assembly from exterior to interior contains:

- Exterior Cladding
- ¾" rainscreen strapping
- 6" Vapour closed XPS insulation
 - Connected with ¾" rainscreen strapping and screws as per manufacturers/engineering specifications
- Airtight WRB
- Structural sheathing
- 2x6 stud wall @ 24" O.C.
- ½" gypsum board
- Interior finish

The roof for drafting and details is the same as with the Tier1 2x6 Assembly. The foundation was drawn as an ICF foundation with 4" of XPS insulation installed to the exterior.

The window installed in the mock-up was the same window as the Tier 1 2x6 Assembly. It was installed to the exterior of the structural sheathing behind the XPS insulation.

The decision to select this assembly was partially influenced by the NRCAN LEEP NZE Wall Guides and the fact that this is a common method of commercial construction. Other influencing factors are that many people in the industry consider this a very sound wall from a building science perspective. Placing the majority or all (when no insulation is installed in the framing cavity) of the insulation to the exterior of the wooden structure helps keep the dew point to the exterior of the structural sheathing and WRB, minimizing the possibility of condensing moisture related damage.

Materials

Materials used for mock-up wall construction are as follows:

Rainscreen Strapping

- o 1x4 SPF lumber & 3/4" Plywood
- Fasteners 10" Simpson Strong-Tie SDWS Exterior Grade Structural Screws – installed per manufacturers guidelines
- Bug screen

• 6" XPS Insulation – Vapour Barrier

o 3 – 2" layers of Owens Corning Foamular NGX Insulation

Airtight WRB

- Membrane Soprema Sopraseal Stick VP Self Adhering Membrane
- o Sill Pan Flashing Soprema Sopraseal Stick Flashpro

Structural Wall

- o 3/8" plywood structural sheathing
- o 2x6 SPF lumber

Assembly Effective Thermal Performance

- o With a R-22 fibreglass batt insulated framing cavity
 - RSI-8.21 or R-46.62
- With an uninsulated framing cavity
 - RSI-5.76 or R-32.70

Construction

Of all the assemblies selected, GBTAC staff found this was the most difficult one to construct. Framing of the structural wall was very straightforward as it is the same process as with the Tier 1 2x6 Assembly. The stud cavity was left uninsulated for the physical mockup but could have been insulated as the amount of exterior XPS insulation utilized maintained an acceptable ratio of insulation to the interior of the VB in Alberta climates as required by the National Building Code - 2023 Alberta Edition.

The air control layer for this assembly was the Soprema self-adhered vapour permeable membrane. Maintaining a continuous air control layer was achieved with this membrane along with the following materials and methods:

- Installation of a strip of WRB on top of the cap plate of the wall at the truss connection, draping to the exterior and interior. Taping the ceiling VB to this membrane
- Expanding spray foam at electrical and mechanical penetrations.
- Adhering WRB to window frame on the sides and the top.
- Foam backer rod and caulking to connect the window frame sill to the WRB at the sill

Using a self-adhering membrane eliminated needing to staple or nail the membrane in place or tape the joints of the WRB. This made the installation of the air control layer slightly faster compared to the Tier 3 assembly.

The most difficult process of constructing the physical mock-up was installation of the 6" of XPS, the rainscreen strapping, and ensuring proper through flashing installation. GBTAC utilized both metal and WRB membrane through wall flashing. When using metal for the through wall flashing, custom pieces had to be made. The length of the screws resulted in more screws wandering out of line while installing them, missing the structural framing member they were intended to hit. One key consideration is that removing a misaligned screw can result in an air leakage path through the WRB and XPS insulation. Misaligned screw penetrations can be found and sealed on the interior side of the structural sheathing.



Custom cap flashing needed to be constructed to finish the top of the XPS insulation at the sill of window. A custom engineered wood window trim return was made for the exterior trim of the window.

Assembly Advantages

- Wrapping the exterior of the wall assembly with insulation reduces the amount of thermal bridging through the assembly.
- Using a vapour closed insulation allowed for the elimination of a VB membrane on the interior of the wall assembly. This saved time on detailing junctions and penetrations.
- Other rigid insulation types could be used if needed such as mineral wool or EPS.
- The structural framing is very similar to how most homes are currently being built (Tier 1 2x6 Assembly).
- Utilizing the WRB as the air control layer allowed for less challenging detailing, and a reduced chance of errors at junctions and penetrations compared to locating the air control layer to the interior of the assembly.
- Attaching the insulation with 3/4" strapping material created a rainscreen for the assembly.
- This assembly is widely considered a safe assembly from a building science perspective by many industry professionals.
- WRB membrane can be utilized as through flashing, helping to reduce thermal bridging that would be caused by using metal through flashing.
- This assembly had the highest calculated effective thermal resistance across all of the selected assemblies for this project when the 2x6 wall cavity was insulated. It had the highest calculated effective thermal resistance of the new build assemblies regardless of whether the 2x6 cavity was insulated or not.
- Any punctures of the air control layer due to misaligned screws from attaching the strapping could be seen and sealed from the inside of the assembly.

Assembly Disadvantages

- High quality membranes, and XPS insulation added a significant cost.
- The self-adhered membranes could be difficult to work with. GBTAC found that a minimum of two installers made installing the membrane go smoothly.
- Once the self-adhered membrane was applied it was very difficult to remove or adjust if needed.
- Some materials could not be found at a common hardware or building supply store and needed to be custom ordered.
- Structural fasteners required for rainscreen and insulation installation were very costly.
- Not all cladding systems can be accommodated with this exact assembly. For example, if stucco was to be installed, there would need to be a sheathing layer to the exterior of the rainscreen or other accommodations made.
- Considerable forethought, planning and organization was required, as missed steps caused considerable delays and extra work.
- There may be difficulty finding trades that can or are willing to install this type
 of assembly in a residential setting.

Cost Analysis


Upon completing a cost analysis of this assembly compared to the Tier 1 2x6 Assembly, the cost to construct this assembly for the model home came out to roughly 160% more.

Of the new build assemblies that were selected, this assembly was the costliest compared to the Tier 1 2x6 Assembly.



Appendix A:

Exterior Foam Net Zero Assembly **Construction Details**






PREMARD IT SAT GETAC.

THIS GRAWING IS THE REQUESTLY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MA
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.

CONTRACTIONS SHALL VERFEY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE PROMING.

EXT. FOAM NZ Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY Drawn LL by LL by BH, NM Date 2025-04-30 Scale 1/2" = 1'- 0" Project Address NI/A

ALBERTA ECOTRUST FOUNDATION



FOUNDATION TRANSITION SECTION DETAIL

2" = 1'-0"

1 VAPOUR IMPERMEABLE BARRIER

2 AIRTIGHT WATER RESISTANT

BARRIER

3 SELF ADHERED MEMBRANE

4 XPS INSULATED BOARD

5 CLADDING

6 FLASHING

7 SEALANT

8 NON-HARDENING SEALANT

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM

11 RAINSCREEN STRAPPING

12 ICF BLOCK

13 RIM BOARD

14 SUBFLOOR

ALBERTA ECOTRUST FOUNDATION

15 PARGING

16 DAMPPROOFING

17 DIMPLE WRAP

18 BATT INSULATION

1301-16 AVENUE NW CALGARY AB, T2M 0L4

PREPARED BY SAT GRIZAC


PREPARED BY SAT GRIZAC

OF THE GOUTHERN ALBERTA HISTITUTE OF TECHNOLOGY GRIZAC OFFICE AND MAKOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WAITTEN CONSENT.

CONTRACTORS SHALL VEREY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCES PRIOR TO CONSTRUCTION.

ON OTI SCALE DENAINING.

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY Drawn LL Checked BH, NM Date 2025-04-30 Scale 2" = 1'- 0"



RECEPTACLE SECTION DETAIL

4" = 1'-0"

11 RAINSCREEN STRAPPING

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT

BARRIER

- 3 SELF ADHERED MEMBRANE
- **4 XPS INSULATED BOARD**
- 5 CLADDING
- 6 FLASHING
- 7 SEALANT
- **8 NON-HARDENING SEALANT**
- 9 COMPRESSED FOAM ROD
- 10 EXPANDING POLYURETHANE SPRAY FOAM

12 IN USE RECEPTACLE ASSEMBLY

13 ELECTRICAL WIRE

14 BATTEN



PREPARED BY SATI GETAL

PREPARED BY SATI GETAL

OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GETAC OFFICE AND MA


NOT BE REPRODUCED OR DISTRICTED WITHOUT THE AUTHORS WEITTEN CONSENT.

CONTRACTORS SHALL VEREFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.

DO NOT SCALE DRAINING.

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY Drawn LL Checked by BH, NM Date 2025-04-30 Scale 4" = 1'- 0" Project Address NA

ALBERTA ECOTRUST FOUNDATION



WINDOW SILL SECTION DETAIL

4" = 1'-0"

1 VAPOUR BARRIER

11 RAINSCREEN STRAPPING

2 AIRTIGHT WATER RESISTANT


BARRIER

- 3 SELF ADHERED MEMBRANE
- 4 XPS INSULATED BOARD
- 5 CLADDING
- 6 FLASHING
- 7 SEALANT
- **8 NON-HARDENING SEALANT**
- 9 COMPRESSED FOAM ROD
- 10 EXPANDING POLYURETHANE SPRAY FOAM

12 GLAZING UNIT


13 WINDOW SUPPORT SHIM

14 BEVELED SLIDING SLOPED DAM



PREPARED BY SATI GETAC
THE SE REPRODUCED OF THE SOUTHERN ALBERTA HISTITUTE OF TECHNOLOGY GETAC OFFICE AND MAY
REPRODUCED OR DESTRUCTED WITHOUT THE AUTHORS WAITTEN CONSENT.
CONTRACTIONS SHALL VEREFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWNING.

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY				
= 1'- 0"				



WINDOW JAMB PLAN DETAIL

4" = 1'-0"

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT

BARRIER

3 SELF ADHERED MEMBRANE

4 XPS INSULATED BOARD

5 CLADDING

6 FLASHING

7 SEALANT

8 NON-HARDENING SEALANT

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM

11 RAINSCREEN STRAPPING


12 GLAZING UNIT

ALBERTA ECOTRUST FOUNDATION

13 FIBREGLASSBATT INSULATION

14 2X2 BLOCK

15 BATTEN




PREPARED BY GMT CETAC.

THIS CRAWNOS IT THE PROPERTY OF THE SOUTHERN ABERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND IAM NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.

CONTRACTIONS SHALL VERREY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCES PRIOR TO CONSTRUCTION.

DO NOT SCALE DRAWNIG.

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY Drawn LL Checked by BH, NM Date 2025-04-30 Scale 4" = 1'- 0" Project Address N/A



WINDOW HEAD SECTION DETAIL

4" = 1'-0"

1 VAPOUR BARRIER

11 RAINSCREEN STRAPPING

12 GLAZING UNIT

13 FIBREGLASS BATT INSULATION

2 AIRTIGHT WATER RESISTANT

BARRIER

3 SELF ADHERED MEMBRANE

4 XPS INSULATED BOARD

5 CLADDING

6 FLASHING

7 SEALANT

8 NON-HARDENING SEALANT

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM



PREPARED BY SAIT GETAC.


THIS CRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GRIAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.

CONTRACTORS SHALL VERFAY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.

ON NOT YOUR DRAWING.

Drawing Ti	tle						
		E '	YT I	\Box	MNZ	7	
		L-/	ハ I . I		NIVI INZ	-	
Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY							
Drawn by	LL	Checked by	BH, NM	Date	2025-04-30	Scale	4" = 1'- 0"
	dress N/A						

ALBERTA ECOTRUST FOUNDATION



FLOOR TO FLOOR TRANSITION SETION DETAIL

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT

BARRIER

1

- 3 SELF ADHERED MEMBRANE
- **4 XPS INSULATED BOARD**
- 5 CLADDING
- 6 FLASHING
- 7 SEALANT
- **8 NON-HARDENING SEALANT**
- 9 COMPRESSED FOAM ROD
- 10 EXPANDING POLYURETHANE SPRAY FOAM

11 RAINSCREEN STRAPPING

12 RIM BOARD

13 SUBFLOOR

14 FIBREGLASS BATT INSULATION

2" = 1'-0"

1301-16 AVENUE NW CALGARY AB, T2M 0L4

PREMARED IN SMIT GETAD

THE REMAINS HIT GETAGE THAT THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GETAC OFFICE AND MAY
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.


CONTRACTORS SHALL VERFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAINING.

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn LL Checked by BH, NM Date 2025-04-30 Scale 2" = 1'- 0"

Project Address N/A

ALBERTA ECOTRUST FOUNDATION



DUCT OPENING SECTION DETAIL

4" = 1'-0"

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT

BARRIER

1

- 3 SELF ADHERED MEMBRANE
- **4 XPS INSULATED BOARD**
- **5 CLADDING**
- 6 FLASHING
- 7 SEALANT
- **8 NON-HARDENING SEALANT**
- 9 COMPRESSED FOAM ROD
- 10 EXPANDING POLYURETHANE SPRAY FOAM

12 DUCT HOOD

13 DUCT

14 BATTEN

1301-16 AVENUE NW CALGARY AB, T2M 0L4

PREPARED BY SAT GRITAD

THE PARED BY SAT GRITAD

THE SOUTHERN ALBERTA, INSTITUTE OF TECHNOLOGY GRITAC OFFICE AND MA
OF THE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN COREIN.

CONTRACTORS SHALL VERBY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PROR TO CONSTRUCTION.
ON TO SCALE DRAWNING.

EXT. FOAM NZ


11 RAINSCREEN STRAPPING

 Project Number
 2024-009
 Project Name
 HIGH PERFORMANCE WALL ASSEMBLY

 Drawn by
 LL
 Checked by
 BH, NM
 Date
 2025-04-30
 Scale
 4" = 1'- 0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION



WALL TO ROOF TRANSITION SECTION DETAIL

ALBERTA ECOTRUST FOUNDATION

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT

BARRIER

1

3 SELF ADHERED MEMBRANE

4 XPS INSULATED BOARD

5 CLADDING

6 FLASHING

7 SEALANT

8 NON-HARDENING SEALANT

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM

11 RAINSCREEN STRAPPING

2" = 1'-0" 12 ROOFING SHINGLE

13 ROOFING UNDERLAYMENT

MEMBRANE

14 ROOFING SHEATHING


15 INSULATION STOP

16 BLOWN INSULATION

17 J-CHANNEL

18 SOFFIT

19 FASCIA




PREPARED BY SAIT GBTAC

ON THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MA
NOT BE REPRODUCED OR DESTRAINED WITHOUT THE AUTHORS WEITTEN CONSENT.


CONTRACTORS SHALL VEREFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCES PRIOR TO CONSTRUCTION.
ON OTI SCALE DRAINING.

EXT. FOAM NZ Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 2" = 1'- 0" Project Address NI/A



PREPARED BY SAIT GETAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MA
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.


Checked by BH, NM 2025-04-30 1/2" = 1'- 0" Project Address N/A ALBERTA ECOTRUST FOUNDATION



PREPARED BY SAIT GETAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MY
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.

1301-16 AVENUE NW CALGARY AB, T2M 0L4

Checked by BH, NM 2025-04-30 1/2" = 1'- 0" Project Address N/A ALBERTA ECOTRUST FOUNDATION



PREPARED BY SAIT GETAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MA
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.

Checked by BH, NM 2025-04-30 1/2" = 1'- 0" Project Address N/A ALBERTA ECOTRUST FOUNDATION



Appendix B:

Wall Assembly Effective Thermal Resistance **Calculations**

Project Name:

High-Performance Wall Assembly Project

Project Address:

Assembly Name:

Fibreglass Batt Insulation filled 2x6 Cavity

Exterior Foam Net Zero Wall Assembly

Materials in Assembly					RSI, (m ² *K)/W	R-Value
Outside Air Film					0.03	0.17
Rainscreen Framing (20mm x 0.0085 RSI/mm)	RSI _F =	0.17	% area of framing =	20	RSI _{Parallel} =	
Rainscreen Air Cavity (20mm)	RSI _C =	0.18	% area of cavity =	80	0.18	1.02
Exterior XPS (152mm)					5.04	28.62
Building Paper					0.00	0.00
OSB Sheathing (9.5mm)					0.0930	0.53
Stud @ 610 (140mm x 0.0085 RSI/mm)	RSI _F =	1.19	% area of framing =	20	RSI _{Parallel} =	
Batt Insulation (R22)	RSI _C =	3.87	% area of cavity =	80	2.67	15.15
Gypsum (12.7mm)		0.8			0.08	0.45
Interior Air Film		57.6			0.12	0.68
			Calculated RSI _E	_{FF} =	8.21	46.62
			9.36 Prescriptive RSI R	equired =	3.08	17.49
			W/HRV		2.97	16.86

Parallel Path Flow Calculations

140mm stud with 140mm Batt Insulation (R22)

$$RSI_{Parallel} = \frac{100}{\frac{20}{1.19} + \frac{80}{3.87}} = 2.67 \quad (m2*K)/W$$

Project Name:

High-Performance Wall Assembly Project

Project Address:

Assembly Name: Exterior Foam Net Zero Wall Assembly		Uninsulated 2x6 Cav		vity		
Materials in Assembly					RSI, (m ² *K)/W	R-Value
Outside Air Film					0.03	0.17
Rainscreen Framing (20mm x 0.0085 RSI/mm)	RSI _F =	0.17	% area of framing =	20	RSI _{Parallel} =	
Rainscreen Air Cavity (20mm)	RSI _C =	0.18	% area of cavity =	80	0.18	1.02
Exterior XPS (152mm)					5.04	28.62
Building Paper					0.00	0.00
OSB Sheathing (9.5mm)					0.0930	0.53
Stud @ 610 (140mm x 0.0085 RSI/mm)	RSI _F =	1.19	% area of framing =	20	RSI _{Parallel} =	
Air Cavity (140mm)	RSI _C =	0.18	% area of cavity =	80	0.22	1.23
Gypsum (12.7mm)		0.8			0.08	0.45
Interior Air Film		57.6			0.12	0.68
			Calculated RSI _{EFF}	=	5.76	32.70
			0.36 D		2.00	47.40
			9.36 Prescriptive RSI Rec	quired =	3.08	17.49
			W/HRV		2.97	16.86

Parallel Path Flow Calculations


140mm stud with 140mm Air Space


$$RSI_{Parallel} = \frac{100}{\frac{20}{1.19} + \frac{80}{0.18}} = 0.22 \quad (m2*K)/W$$




Appendix C:


Cost Analysis Model Home









COLUMN DETAIL SCALE: 3/8" = 1'-0"





SCALE: 3/16" = 1'-0"











ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV: DECK:	1440 sq.ft. REVISIONS: 700 sq.ft. 740 sq.ft. N/A sq	MODEL: 2 STOREY ELEVATION: GRAFTSMAN PAGE 2 OF 10

UNPROTECTED OPENINGS


LIMITING DISTANCE: ALLOWABLE OPENINGS: EXPOSED BUILDING FACE: UNPROTECTED OPENINGS: ACTUAL OPENINGS: 3,08 m 9,00 % 743,33 sq.ft. 46,84 sq.ft. 6,30%




ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV:	1440 sq.ft. 700 sq.ft. 740 sq.ft. N/A sq.ft. N/A sq.ft.	MODEL: 2 STOREY ELEVATION: CRAFTSMAN
DECK:	N/A sq.ft.	PAGE 3 OF 10

UNPROTECTED OPENINGS

LIMITING DISTANCE: ALLOWABLE OPENINGS: EXPOSED BUILDING FACE: UNPROTECTED OPENINGS: ACTUAL OPENINGS: 1.22 m T.00 % T39.05 eq.ft. 27.50 eq.ft. 3.72%



ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV:	1440 sq.ft. REVISIONS: 700 sq.ft. 740 sq.ft. N/A sq.ft.	MODEL: 2 STOREY ELEVATION: CRAFTSMAN
DECK:	N/A sq.ft. N/A sq.ft.	PAGE 4 OF 10






STANDARD WALL SCONCE HEIGHT AT LANDING OR RISERS: 6'-8"

ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV:	1440 sq.ft. 700 sq.ft. 740 sq.ft. N/A sq.ft.	MODEL: Z STOREY ELEVATION: CRAFTSMAI
DECK:	N/A sq.ft. N/A sq.ft.	PAGE 5 0

NOTE: MAIN FLOOR WINDOWS TO BE 7'-11" HIGH UNLESS OTHERWISE NOTED 41'-0" 35'-0" 6'-0" 3'-72" 13'-91" 5'-68" 10'-4" -2×6 FULL HEIGHT FURRING WALL 9 16" O.C. 2'-5' 10-4 - 6x6 POST BUILT UP COLUMN, SEE DETAIL ALUMINUM RAILING - 12" DROPPED BULKHEAD FRIDGE RECESS SEE DETAIL TRUSSES OTR MICRO 11 7/8" ENG. FLOOR JOISTS SPACING AS PER SUPPLIER CANT. DINING AREA LIFESTYLE ROOM 9'-9" x 12'-2" 12'-9" x 12'-0" II" FLUSH EATING BAR 3'-31" 4'-61" 5'-9½" 3'-2" 42" HIGH STUBWALL PASSAGE. OPEN TO ABOVE PANTRY 42" POURED CONCRETE WALKWAY 5'-0" PAPER ALUMINUM RAILING ENG. HEADER 40/24 P T/O WINDOW-TO MATCH T/O DOOR/ TRANSOM ENG. WALL, -SEE DETAIL 14" WIDE x 6" DEEP DROPPED BULKHEAD - 60"x40 PRECAST CONCRETE LANDING 11'-10\frac{1}{2}" 1-9" 2'-9" 2'-11" 2'-0" CANT. 5-68" 13'-71" 4'-5" 4'-8" 5'-8" 35'-0" MAIN FLOOR PLAN WIDTH TO VARY SCALE: 3/16" = 1'-0" NOTE: DIMENSIONS ARE TO FINISHED MATERIAL ADDRESS: PASSAGE DETAIL FRIDGE RECESS DETAIL MAIN 1440 sq.ft. REVISIONS: TOTAL AREA: MODEL: 2 STOREY 700 sq.ft. 740 sq.ft. MAIN FLOOR: SCALE: 3/16" = 1'-0" SCALE: 3/16" - 1'-0" ELEVATION:


UPPER FLOOR: GARAGE: N/A sq.ft. CRAFTSMAN BSMNT DEV: DECK: N/A sq.ft. N/A sq.ft. PAGE 6 OF 10 NOTE: UPPER FLOOR WINDOWS TO BE 6'-11" HIGH





ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV:	1440 sq.ft. 700 sq.ft. 740 sq.ft. N/A sq.ft.	MODEL: 2 STOREY ELEVATION: GRAFTSMAN
DECK:	N/A sq.ft. N/A sq.ft.	PAGE 7 OF 10

NOTE: MAIN FLOOR WINDOWS TO BE T'-11" HIGH UNLESS UPPER FLOOR WINDOWS TO BE 6'-11" HIGH UNLESS OTHERWISE NOTED



- ENERGY FIODEL DETAILS
 -SPECIFICATIONS, CHANGE REQUESTS SHALL OVERRIDE PLANS
 -FINAL GRADING AND SITE CONDITIONS MAY VARY EXTERIOR APPEARANCE
 -SECTION NOTES ARE GENERAL AND MAY VARY OR NOT APPLY TO ALL PLANS

- -ALUMINUM FASCIA AND EAVESTROUGH AS NOTED
 -ALUMINUM VENTED SOFFIT ON FRONT AND REAR ELEVATIONS ONLY.
 -NON-VENTED ALUMINUM SOFFIT ON SIDE ELEVATIONS
 -TRUSS MANUFACTURER TO VERIFY ALL ROOF SLOPES AND TRUSS DESIGN PRIOR TO FABRICATION

- -TRUSS MANUFACTURER TO VERIFY ALL ROOF SLOPES AND TRUSS DESIGN PRIOR TO FALINTEL NOTES:
 -ALL EXTERIOR LINTELS TO BE 2-2×IØ SPF UNLESS NOTED
 -ALL LINTELS OVER 6'-Ø" MUST HAVE A DOUBLE CRIPPLE
 -INSULATE 4 DRYWALL WALLS WITHIN 4'Ø" OF FURNACE 4 HUT
 -INSULATE 4 DRYWALL WALLS ADJACENT TO STAIRS AND LANDING
 -INSULATE AND DRYWALL WALLS AT BASEMENT LAUNDRY WHEN APPLICABLE
 -ANY DISCREPANCIES TO BE REPORTED TO THE DESIGNER PRIOR TO CONSTRUCTION

ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV: DECK:	700 sq.rt.	MODEL: 2 STOREY ELEVATION: CRAFTSMAN PAGE 8 OF 10



Appendix D:

Wall Assembly Affordability and Constructability Analysis

Cost per sq/ft of Wall Affordability Analysis						
Assembly	Cost/sqft of Wall	Notes				
Tier 1 2x6	Baseline Cost	Assembly built with materials commonly used in current residential construction. These include; • Tyvek WRB. • 6 mil poly vapour barrier.				
Exterior Mineral Wool Tier 3	153% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; • Siga Majvest WRB (Roughly twice as much per sq/ft coverage of Tyvek). • Siga Majrex vapour barrier (roughly 9x as much per sq/ft coverage of 6 mil poly). • Siga WRB and VB tapes for air sealing. Other Additional Costs: • Exterior mineral wool insulation. • Rainscreen material.				
Double Stud Net Zero	64% higher than baseline	Incorporates a combination of more commonly used construction materials and high-performance building materials at an additional cost. These include; • Typar WRB (similar in price to Tyvek). • Siga Majrex vapour barrier (roughly 9x as much per sq/ft coverage of 6 mil poly). • Siga VB tapes for air sealing. Other Additional Costs: • Framing of 2 walls. • Additional insulation to fill wall cavity.				
Exterior Foam Net Zero	465% higher than baseline	Incorpotates high-performance building materials at an additional cost. These include; • Soprema Sopraseal Stick WRB (Roughly 11x as much per sq/ft coverage of Tyvek). •Soprema sill flashing. Other Additional Costs: • Exterior XPS insulation. • Rainscreen material. • Fasteners for screwing through a large amount of insulation.				
Fire Resistant Retrofit	206% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; • ProClima Mento WRB (Roughly 3x as much per sq/ft coverage of Tyvek. • ProClima tapes for air sealing. Other Additional Costs: • Exterior mineral wool insulation. • Rainscreen material. • Thermal Clips.				
Larsen Truss Retrofit	165% higher than baseline	Incorporates common building materials similar to the baseline home; • Typar WRB (similar cost as Tyvek). Additional Costs: • Framing material for the Larsen Truss. • Rainscreen material. • WRB tape for air sealing. • Insulation for Larsen Truss cavity. • Soprema liquid applied membrane for window bucks and air sealing.				

- No monetary value has been noted as there are many variables that could impact the comparability of these costs.
- This chart is a direct comparison of the cost of the material to construct **ONLY** the wall assembly of the model home.
- This chart only compares the materials selected for each physical mock-up. It cannot be considered a 1 to 1 comparison as different
 materials selected have different costs, possibly resulting in inflated prices for certain assemblies.

Constructability Analysis							
Assembly	Material Availability	Difficulties/Issues	Constructability Rating (1-5)				
Tier 1 2x6	All material used was available at common hardware/construction material supply stores. Material was all readily available as this is a commonly built assembly across Alberta.	Accoustical sealant can be messy and inconsistent.	1 Baseline •Easiest to construct.				
Exterior Mineral Wool Tier 3	Framing and cavity insulation materials were readily available at common hardware/material supply stores. SIGA WRB, VB and tapes was not readily available and needed to be ordered in. This required a small lead time. Exterior mineral wool insulation was not readily available and needed to be ordered. This required a significant lead time. Rainscreen framing material and fasteners were readily available at common stores. Custom made flashing was required. GBTAC made these on site with the use of a Break. If GBTAC did not have this tool, this material would need to be custom ordered.	strapping properly embed in a structural member of the wall. • Ensuring proper flashing installation and detailing around the window. • Custom exterior window trim detail was required.	Relatively simple to construct. Exterior insulation is the major change from the baseline that makes it more difficult				
Double Stud Net Zero	VB and tapes was not readily available and needed to be ordered in. This required a small lead time.	be wrapped under the plates of the walls before the walls are installed.	2 • Simple Construction . • Not to dissimilar to the baseline with adding a second wall and extra insulation increasing the difficulty.				
Exterior Foam Net Zero	Framing material readily available at common hardware/material supply stores. WRB was not readily available and needed to be ordered in. This required a small lead time. XPS and fasteners were readily available at some material supply stores, but had the possibility to need to be ordered in with a small lead time. Custom flashing needed to be made. This was made onsite with a break, otherwise this would have been needed to be ordered from a supplier.	WRB was the air control layer, so ensuring continuous membrane behind flashings and penetrations increased the difficulty of installing the WRB. Ensuring the screws that hold on the rainscreen strapping properly embed in a structural member of the wall. Ensuring proper flashing installation and detailing around the window. Custom exterior window trim detail was required. Installing through flashing in the correct spot at the wall proved difficult. Peel and stick membrane required at least 2 workers to install as it was difficult to remove the backing without adhering the membrane to itself.	• Most difficult to construct. • Long screws and the amount of exterior insulation made this assembly difficult to construct.				
Fire Resistant Retrofit	ProClima WRB and tapes wer not readily available and needed to be ordered in. This required a small lead time. Exterior mineral wool insulation was not readily available and needed to be ordered. This required a significant lead time. Rainscreen framing material and fasteners were readily available at common stores. Custom made flashing was required. GBTAC made these on site with the use of a Break. If GBTAC did not have this tool, this material would need to be custom ordered. Soprema thermal clips had to be ordered in with minimal lead time.	Attaching the rainscreen strapping to the metal thermal clips proved quite difficult at times.	• Somewhat difficult to construct. • If good screws are used that screw into the metal thermal clips well, the construction would be slightly easier.				
Larsen Truss Retrofit	All framing material and the WRB material was readily available at common hardware/material supply stores. Dense pack cellulose needed to be installed by a professional installer. Lead time for booking the installer was required. Liquid applied membrane for window bucks was required to be ordered in with a small lead time.	Installing the liquid applied membrane could not be done at a lower temperature.	2.5 Relatively simple to construct. Amount of labour and correct installation of the Larsen Truss raises the difficulty.				

Exterior Foam Net Zero Assembly



















