

Fire Resistant Retrofit Assembly

See **Appendix A: Fire Resistant Retrofit Assembly Construction Details** for plans and construction details.

Description & Overview

This assembly was approached as if there was only an exterior retrofit being performed on an existing home from the mid twentieth century. All the structural components were staying as-is and an exterior high-performance retrofit was going to take place. To determine what material to include in the physical mock-up that would represent the existing construction, GBTAC staff previous experience in renovations guided the selection. The existing assembly from exterior to interior contains:

- 3/8 plywood structural sheathing
- 2x4 stud wall with R-12 fibreglass batt insulation
- Polyethylene sheet VB

To determine what the high-performance retrofit additions would include, GBTAC staff utilized information from previously completed retrofit projects, and staff knowledge. The final decision was to display the addition of mineral wool to the exterior of the existing structure with a new airtight WRB and window replacement. The exterior retrofit addition, from exterior to interior contains:

- Exterior cladding
- 3/4" Rainscreen strapping
- 4" Mineral wool insulation
- Airtight WRB

For the roof assembly it was determined that a 2x6 rafter was a very common way to build roofs. The existing foundation was considered to be a cast in place concrete foundation wall with a 1" airspace, then a 2x4 stud framed wall with R-12 fibreglass batt insulation and a polyethylene VB.

The window installed in the mock-up is the same as the Tier 1 2x6 Assembly.

Materials

Materials used for mock-up wall construction are as follows:

- **Rainscreen Strapping**
 - 1x4 SPF lumber
 - Strapping/Insulation Attachment - Soprema 4" ACS Thermal Clips
- **4" Mineral wool**
 - 2 – 2" layers of Owens Corning Thermafiber Insulation
- **Airtight WRB**
 - Membrane – Pro Clima Solitex Mento – Mechanically Fastened
 - Sealing tape – Siga Wigluv in varying sizes.
 - Sill Pan Flashing – Soprema Sopraseal Stick Flashpro
- **Existing Structural Wall**
 - 3/8" Plywood structural sheathing
 - 2x4 SPF lumber
- **Cavity Insulation**
 - Owens Corning R-12 Pink Next gen Fiberglass Insulation
- **Vapour Barrier**
 - Existing polyethylene plastic sheeting

- **Assembly Effective Thermal Performance**
 - RSI-4.81 or R-27.32

Construction


See **Exterior Mineral Wool Tier 3 Assembly – Construction** for the construction methods.

This assembly can be closely compared to constructing the Exterior Mineral wool Tier 3 Assembly, with 2” extra mineral wool, and no structural framing. The air control layer for this assembly was the Pro Clima Solitex Mento membrane. Maintaining a continuous air control layer was achieved with this membrane along with the following materials and methods:

- Taping to seal all joints and openings in the WRB.
- Installation of closed cell spray foam insulation at the wall to rafter connection, sealing WRB to ceiling poly.
- Seal WRB to foundation with a sealant that works with the membrane and concrete.
- Taping electrical wire penetrations.
- Taping WRB to window frame on the sides and the top.
- Taping WRB to mechanical penetrations
- Foam backer rod and caulking to connect the window frame sill to the WRB at the sill.

In order to achieve a fire-resistant assembly, mineral wool insulation was used with a thermally broken Z clip (See **Error! Reference source not found.**) to support the insulation and rainscreen strapping.

Figure 1: Soprema ACS Thermal Clip



Assembly Advantages

- Wrapping the exterior of the wall assembly with insulation reduces the amount of thermal bridging through the wood structural framing members.
- Mineral wool has fire-resistant qualities making this assembly useful for areas with fire requirements.
- Other rigid insulation types can be used if needed such as XPS or EPS if a fire-resistant assembly is not needed.
- Retrofitting an existing home saves waste and new construction costs.
- Utilizing the WRB as the air control layer allowed for less detailing, and a reduced chance of errors at junctions when the air control layer is to the interior of the assembly.



SAIT Green Building Technologies – High Performance Wall Assembly Project

- Attaching the insulation with $\frac{3}{4}$ " strapping material created a rainscreen for the assembly, assisting with assembly drying.
- WRB membrane could be utilized as trough flashing, helping to reduce thermal bridging that would be caused by using metal through flashing.
- Using Z girt clips were easy and quick to install on the wall and reduced the chance of missing a structural member which would puncture the air control layer.

Assembly Disadvantages

- Some materials could not be found at a common hardware or building supply store and needed to be custom ordered.
- Self-tapping screws were required to attach the strapping to the clips. This led to some difficulty fastening the strapping occasionally.
- Not all cladding systems can be accommodated with this exact assembly. For example, if stucco was to be installed, there would need to be a sheathing layer to the exterior of the rainscreen or other accommodations made.
- There may be difficulty finding trades that can or are willing to install this type of assembly in a residential setting.
- Air sealing of the attic poly VB is encouraged to be completed as part of a whole building retrofit, which can be a very difficult and arduous task to complete.

Cost Analysis

The cost analysis revealed that completing a retrofit with this assembly for the model home would cost roughly 7% more compared to constructing the home with the Tier 1 2x6 Assembly.

Of the two retrofit examples, this assembly was the costlier of the two.

GBTAC found that the largest cause of additional costs was due to the use of the high quality WRB membrane, and the mineral wool insulation.


Appendix A:

Fire Resistant Retrofit Assembly Construction Details

FIRE RESISTANT RETROFIT ASSEMBLY

EFFECTIVE RSI = 4.81; R-VALUE = 27.32

- EXTERIOR CLADDING
- 1X3 RAIN SCREEN
- 4" EXTERNAL MINERAL WOOL
- AIRTIGHT WATER RESISTANT BARRIER
- EXISTING 3/8" EXTERIOR SHEATHING
- EXISTING 2X4 STUD w/ FIBERGLASS INSULATION
- EXISTING VAPOUR BARRIER
- EXISTING 1/2" GYPSUM BOARD
- EXISTING INTERIOR FINISH



ENVELOPE SECTION

1/2" = 1'-0"

Drawing Title

FIRE RESISTANT RETROFIT

Project Number

2024-009

Project Name

HIGH PERFORMANCE WALL ASSEMBLY

Drawn by

MS, NM

Checked by

BH, NM

Date

2025-04-30

Scale

2" = 1'-0"


Project Address

N/A

Issued For

ALBERTA ECOTRUST FOUNDATION

1.01




1

FOUNDATION TRANSITION SECTION DETAIL

2" = 1'-0"

- | | | |
|---------------------------------------|---------------|-----------------------------------|
| 1 VAPOUR BARRIER | 11 BUG SCREEN | 12 CONCRETE FOUNDATION |
| 2 AIRTIGHT WATER RESISTANT BARRIER | | 13 DAMPPROOFING |
| 3 SELF ADHERED MEMBRANE | | 14 PARGING |
| 4 EXISTING FIBREGLASS BATT INSULATION | | 15 RIM BOARD |
| 5 CLADDING | | 16 SUBFLOOR |
| 6 FLASHING | | 17 THERMALLY BROKEN Z GIRT SYSTEM |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by MS Checked by BH, NM Date 2025-04-30 Scale 2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.02

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

RECEPTACLE SECTION DETAIL

4" = 1'-0"

- | | | |
|---------------------------------------|-------------------------|-------------------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 12 IN USE RECEPTACLE ASSEMBLY |
| 2 AIRTIGHT WATER RESISTANT BARRIER | | 13 BATTEN |
| 3 SELF ADHERED MEMBRANE | | 14 ELECTRICAL WIRE |
| 4 EXISTING FIBERGLASS BATT INSULATION | | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by MS Checked by BH, NM Date 2025-04-30 Scale 2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.03

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.



1

WINDOW SILL SECTION DETAIL

4" = 1'-0"

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT
BARRIER

3 SELF ADHERED MEMBRANE

4 EXISTING FIBERGLASS BATT INSULATION

5 CLADDING

6 FLASHING

7 SEALANT

8 NON-HARDENING SEALANT

9 COMPRESSED FOAM ROD


10 EXPANDING POLYURETHANE SPRAY FOAM

11 GLAZING UNIT

12 WINDOW SUPPORT SHIM

13 BEVELED SIDING SLOPED DAM

14 THERMALLY BROKEN Z GIRT
SYSTEM



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number

2024-009

Project Name

HIGH PERFORMANCE WALL ASSEMBLY

Drawn by

MS

Checked by

BH, NM

Date

2025-04-30

Scale

4" = 1'-0"

Project Address


N/A

Issued For

ALBERTA ECOTRUST FOUNDATION

1.04

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

WINDOW JAMB PLAN DETAIL

4" = 1'-0"

- | | | |
|---------------------------------------|-------------------------|---------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 12 GLAZING UNIT |
| 2 AIRTIGHT WATER RESISTANT BARRIER | | 13 CLOSURE FLASHING |
| 3 SELF ADHERED MEMBRANE | | |
| 4 EXISTING FIBREGLASS BATT INSULATION | | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by MS Checked by BH, NM Date 2025-04-30 Scale 4" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.05

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.



1

WINDOW HEAD SECTION DETAIL

4" = 1'-0"

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT
BARRIER

3 SELF ADHERED MEMBRANE

4 EXISTING FIBREGLASS BATT INSULATION

5 CLADDING

6 FLASHING

7 SEALANT

8 NON-HARDENING SEALANT


9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM

11 RAINSCREEN STRAPPING

12 GLAZING UNIT

13 BUG SCREEN



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number

2024-009

Project Name

HIGH PERFORMANCE WALL ASSEMBLY

Drawn by

MS

Checked by

BH, NM

Date

2025-04-30

Scale

4" = 1'-0"

Project Address


N/A

Issued For

ALBERTA ECOTRUST FOUNDATION

1.06

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

FLOOR TO FLOOR TRANSITION SETION DETAIL

2" = 1'-0"

- | | | |
|---------------------------------------|-----------------------------------|--------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 12 RIM BOARD |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 THERMALLY BROKEN Z GIRT SYSTEM | 13 SUBFLOOR |
| 3 SELF ADHERED MEMBRANE | | |
| 4 EXISTING FIBREGLASS BATT INSULATION | | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by MS Checked by BH, NM Date 2025-04-30 Scale 1/2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.07

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

DUCT OPENING SECTION DETAIL

4" = 1'-0"

- | | | |
|---------------------------------------|-------------------------|---------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 12 DUCT HOOD |
| 2 AIRTIGHT WATER RESISTANT BARRIER | | 13 DUCT |
| 3 SELF ADHERED MEMBRANE | | 14 BATTEN |
| 4 EXISTING FIBREGLASS BATT INSULATION | | 15 BUG SCREEN |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by MS Checked by BH, NM Date 2025-04-30 Scale 4" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.08

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

WALL TO ROOF TRANSITION SECTION DETAIL

2" = 1'-0"

- | | | |
|--------------------------------------|-----------------------------------|----------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 13 J-CHANNEL |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 THERMALLY BROKEN Z GIRT SYSTEM | 14 SOFFIT |
| 3 SELF ADHERED MEMBRANE | | 15 ROOFING SHEATHING |
| 4 EXISTING ATTIC INSULATION | | 16 ROOFING MEMBRANE |
| 5 CLADDING | | 17 ROOFING SHINGLE |
| 6 FLASHING | | 18 FASCIA |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by MS Checked by BH, NM Date 2025-04-30 Scale 1/2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.09

PREPARED BY SAI GTAC.
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY (SAIT) OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.


FIRE RESISTANT RETROFIT ASSEMBLY

EFFECTIVE RSI = 4.81 ; R-VALUE = 27.32

- EXTERIOR CLADDING
- 1X3 RAIN SCREEN
- 4" EXTERNAL MINERAL WOOL
- AIRTIGHT WATER RESISTANT BARRIER
- EXISTING $\frac{3}{8}$ " EXTERIOR SHEATHING
- EXISTING 2X4 STUD w/ FIBERGLASS INSULATION
- EXISTING VAPOUR BARRIER
- EXISTING $\frac{1}{2}$ " GYPSUM BOARD
- EXISTING INTERIOR FINISH

LEGEND

— AIR BARRIER



1

AIR BARRIER CONTINUITY

1/2" = 1'-0"

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by MS Checked by BH, NM Date 2025-04-30 Scale 1/2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.10

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.


FIRE RESISTANT RETROFIT ASSEMBLY

EFFECTIVE RSI = 4.81; R-VALUE = 27.32

- EXTERIOR CLADDING
- 1X3 RAIN SCREEN
- 4" EXTERNAL MINERAL WOOL
- AIRTIGHT WATER RESISTANT BARRIER
- EXISTING 3/8" EXTERIOR SHEATHING
- EXISTING 2X4 STUD w/ FIBERGLASS INSULATION
- EXISTING VAPOUR BARRIER
- EXISTING 1/2" GYPSUM BOARD
- EXISTING INTERIOR FINISH

LEGEND

VAPOUR BARRIER



1

VAPOUR BARRIER CONTINUITY

1/2" = 1'-0"

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number

2024-009

Project Name

HIGH PERFORMANCE WALL ASSEMBLY

Drawn by

MS

Checked by

BH, NM

Date

2025-04-30

Scale

1/2" = 1'-0"

Project Address

N/A

Issued For

ALBERTA ECOTRUST FOUNDATION

1.11


FIRE RESISTANT RETROFIT ASSEMBLY

EFFECTIVE RSI = 4.81; R-VALUE = 27.32

- EXTERIOR CLADDING
- 1X3 RAIN SCREEN
- 4" EXTERNAL MINERAL WOOL
- AIRTIGHT WATER RESISTANT BARRIER
- EXISTING $\frac{3}{8}$ " EXTERIOR SHEATHING
- EXISTING 2X4 STUD w/ FIBERGLASS INSULATION
- EXISTING VAPOUR BARRIER
- EXISTING $\frac{1}{2}$ " GYPSUM BOARD
- EXISTING INTERIOR FINISH

LEGEND

— WATER BARRIER



1

WATER BARRIER CONTINUITY

1/2" = 1'-0"

Drawing Title

FIRE RESISTANT ASSEMBLY

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by MS Checked by BH, NM Date 2025-04-30 Scale 1/2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.12

Appendix B:

Wall Assembly Effective Thermal Resistance Calculations

Project Name:

High-Performance Wall Assembly Project

Project Address:

Assembly Name:

Fire Resistant Retrofit Wall Assembly

Materials in Assembly				RSI, (m ² *K)/W	R-Value
Outside Air Film				0.03	0.17
Rainscreen Framin (20mm x 0.0085 RSI/mm)	RSI _F =	0.17	% area of framing =	23	RSI _{parallel} =
Rainscreen Air Cavity (20mm)	RSI _C =	0.18	% area of cavity =	77	
Exterior Mineral Wool (102mm)				2.81	15.96
Building Paper				0.00	0.00
OSB Sheathing (9.5mm)				0.0930	0.53
Stud @ 406mm O.C. (89mm x 0.0085 RSI/mm)	RSI _F =	0.76	% area of framing =	23	RSI _{parallel} =
Batt Insulation (89mm)(R12)	RSI _C =	2.11	% area of cavity =	77	
Gypsum (12.7mm)				0.08	0.45
Interior Air Film				0.12	0.68
				Calculated RSI _{EFF} =	4.81
				9.36 Prescriptive RSI Required =	17.49
				W/HRV	16.86

Parallel Path Flow Calculations


89mm stud with 89mm Batt Insulation (R12)

$$RSI_{\text{Parallel}} = \frac{100}{\frac{23}{0.76} + \frac{77}{2.11}} = 1.50 \quad (\text{m}^2 \cdot \text{K})/\text{W}$$

Appendix C:


Cost Analysis Model Home

	ADDRESS:		
	TOTAL AREA:	1440 sq.ft.	REVISIONS:
	MAIN FLOOR:	700 sq.ft.	
	UPPER FLOOR:	740 sq.ft.	
	GARAGE:	N/A sq.ft.	
	BSMNT DEV:	N/A sq.ft.	
DECK:	N/A sq.ft.		
MODEL: 2 STOREY			
ELEVATION: CRAFTSMAN			
PAGE 1 OF 10			




ADDRESS:			<div></div>	
TOTAL AREA:	1440 sq.ft.	REVISIONS:	MODEL: 2 STOREY	
MAIN FLOOR:	700 sq.ft.		ELEVATION:	
UPPER FLOOR:	740 sq.ft.		CRAFTSMAN	
GARAGE:	N/A sq.ft.		PAGE 2 OF 10	
BSMNT DEV:	N/A sq.ft.			
DECK:	N/A sq.ft.			

LIMITING DISTANCE:	3.08 m
ALLOWABLE OPENINGS:	9.00 %
EXPOSED BUILDING FACE:	743.33 sq.ft.
UNPROTECTED OPENINGS:	46.24 sq.ft.
ACTUAL OPENINGS:	6.30%



UNPROTECTED OPENINGS

LIMITING DISTANCE:	122 m
ALLOWABLE OPENINGS:	7.00 %
EXPOSED BUILDING FACE:	139.05 sq.ft.
UNPROTECTED OPENINGS:	21.50 sq.ft.
ACTUAL OPENINGS:	3.12%



RIGHT ELEVATION

SCALE: 3/16" = 1'-0"

ADDRESS:


TOTAL AREA: 1440 sq.ft.
MAIN FLOOR: 700 sq.ft.
UPPER FLOOR: 740 sq.ft.
GARAGE: N/A sq.ft.
BSMNT DEV: N/A sq.ft.
DECK: N/A sq.ft.

REVISIONS:


MODEL: 2 STOREY
ELEVATION:
CRAFTSMAN

PAGE 4 OF 10


NOTE:
MAIN FLOOR WINDOWS
TO BE 7'-11" HIGH UNLESS
OTHERWISE NOTED



MAIN FLOOR PLAN
SCALE: 3/16" = 1'-0"



PASSAGE DETAIL
MAIN
SCALE: 3/16" = 1'-0"




FRIDGE
RECESS DETAIL
SCALE: 3/16" = 1'-0"


NOTE:
DIMENSIONS ARE
TO FINISHED MATERIAL

ADDRESS:			
TOTAL AREA:	1440 sq.ft.	REVISIONS:	MODEL: 2 STOREY ELEVATION: CRAFTSMAN
MAIN FLOOR:	700 sq.ft.		
UPPER FLOOR:	740 sq.ft.		
GARAGE:	N/A sq.ft.		
BSMNT DEV:	N/A sq.ft.		
DECK:	N/A sq.ft.		
			PAGE 6 OF 10

NOTE:
UPPER FLOOR WINDOWS
TO BE 6'-11" HIGH




UPPER FLOOR PLAN
SCALE: 3/16" = 1'-0"



ADDRESS:					
TOTAL AREA:		1440 sq.ft.	REVISIONS:		MODEL: 2 STOREY ELEVATION: CRAFTSMAN PAGE 7 OF 10
MAIN FLOOR:		700 sq.ft.			
UPPER FLOOR:		740 sq.ft.			
GARAGE:		N/A sq.ft.			
BSMNT DEV:		N/A sq.ft.			
DECK:		N/A sq.ft.			

NOTE:
MAIN FLOOR WINDOWS TO
BE 7'-11" HIGH UNLESS
OTHERWISE NOTED

UPPER FLOOR WINDOWS
TO BE 6'-11" HIGH UNLESS
OTHERWISE NOTED



GENERAL NOTES:

- ALL CONSTRUCTION TO CONFORM TO CURRENT A.B.C., FIRE CODES AND 936 PERFORMANCE ENERGY MODEL DETAILS
 - SPECIFICATIONS, CHANGE REQUESTS SHALL OVERRIDE PLANS
 - FINAL GRADING AND SITE CONDITIONS MAY VARY EXTERIOR APPEARANCE
 - SECTION NOTES ARE GENERAL AND MAY VARY OR NOT APPLY TO ALL PLANS
 - ALUMINUM FASCIA AND EAVESTROUGH AS NOTED
 - ALUMINUM VENTED SOFFIT ON FRONT AND REAR ELEVATIONS ONLY.
 - NON-VENTED ALUMINUM SOFFIT ON SIDE ELEVATIONS
 - TRUSS MANUFACTURER TO VERIFY ALL ROOF SLOPES AND TRUSS DESIGN PRIOR TO FABRICATION
- LINTEL NOTES:**
- ALL EXTERIOR LINTELS TO BE 2-2x10 SFF UNLESS NOTED
 - ALL LINTELS OVER 6'-0" MUST HAVE A DOUBLE CRIPPLE
 - INSULATE 4 DRYWALL WALLS WITHIN 4'-0" OF FURNACE 4 HUT
 - INSULATE 4 DRYWALL WALLS ADJACENT TO STAIRS AND LANDING
 - INSULATE AND DRYWALL WALLS AT BASEMENT LAUNDRY WHEN APPLICABLE
 - ANY DISCREPANCIES TO BE REPORTED TO THE DESIGNER PRIOR TO CONSTRUCTION

CROSS SECTION A
SCALE: 3/16" = 1'-0"

ADDRESS:

TOTAL AREA: 1440 sq.ft.
MAIN FLOOR: 700 sq.ft.
UPPER FLOOR: 740 sq.ft.
GARAGE: N/A sq.ft.
BSMNT DEV: N/A sq.ft.
DECK: N/A sq.ft.

REVISIONS:

MODEL: 2 STOREY
ELEVATION:
CRAFTSMAN
PAGE 8 OF 10

Appendix D:

Wall Assembly Affordability and Constructability Analysis

Cost per sq/ft of Wall Affordability Analysis

Assembly	Cost/sqft of Wall	Notes
Tier 1 2x6	Baseline Cost	Assembly built with materials commonly used in current residential construction. These include; <ul style="list-style-type: none"> • Tyvek WRB. • 6 mil poly vapour barrier.
Exterior Mineral Wool Tier 3	153% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; <ul style="list-style-type: none"> • Siga Majvest WRB (Roughly twice as much per sq/ft coverage of Tyvek). • Siga Majrex vapour barrier (roughly 9x as much per sq/ft coverage of 6 mil poly). • Siga WRB and VB tapes for air sealing. Other Additional Costs: <ul style="list-style-type: none"> • Exterior mineral wool insulation. • Rainscreen material.
Double Stud Net Zero	64% higher than baseline	Incorporates a combination of more commonly used construction materials and high-performance building materials at an additional cost. These include; <ul style="list-style-type: none"> • Typar WRB (similar in price to Tyvek). • Siga Majrex vapour barrier (roughly 9x as much per sq/ft coverage of 6 mil poly). • Siga VB tapes for air sealing. Other Additional Costs: <ul style="list-style-type: none"> • Framing of 2 walls. • Additional insulation to fill wall cavity.
Exterior Foam Net Zero	465% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; <ul style="list-style-type: none"> • Soprema Sopraseal Stick WRB (Roughly 11x as much per sq/ft coverage of Tyvek). • Soprema sill flashing. Other Additional Costs: <ul style="list-style-type: none"> • Exterior XPS insulation. • Rainscreen material. • Fasteners for screwing through a large amount of insulation.
Fire Resistant Retrofit	206% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; <ul style="list-style-type: none"> • ProClima Mento WRB (Roughly 3x as much per sq/ft coverage of Tyvek). • ProClima tapes for air sealing. Other Additional Costs: <ul style="list-style-type: none"> • Exterior mineral wool insulation. • Rainscreen material. • Thermal Clips.
Larsen Truss Retrofit	165% higher than baseline	Incorporates common building materials similar to the baseline home; <ul style="list-style-type: none"> • Typar WRB (similar cost as Tyvek). Additional Costs: <ul style="list-style-type: none"> • Framing material for the Larsen Truss. • Rainscreen material. • WRB tape for air sealing. • Insulation for Larsen Truss cavity. • Soprema liquid applied membrane for window bucks and air sealing.

- No monetary value has been noted as there are many variables that could impact the comparability of these costs.
- This chart is a direct comparison of the cost of the material to construct **ONLY** the wall assembly of the model home.
- This chart only compares the materials selected for each physical mock-up. It cannot be considered a 1 to 1 comparison as different materials selected have different costs, possibly resulting in inflated prices for certain assemblies.

Constructability Analysis

Assembly	Material Availability	Difficulties/Issues	Constructability Rating (1-5)
Tier 1 2x6	<ul style="list-style-type: none"> All material used was available at common hardware/construction material supply stores. Material was all readily available as this is a commonly built assembly across Alberta. 	<ul style="list-style-type: none"> Accoustical sealant can be messy and inconsistent. 	1 Baseline <ul style="list-style-type: none"> Easiest to construct.
Exterior Mineral Wool Tier 3	<ul style="list-style-type: none"> Framing and cavity insulation materials were readily available at common hardware/material supply stores. SIGA WRB, VB and tapes was not readily available and needed to be ordered in. This required a small lead time. Exterior mineral wool insulation was not readily available and needed to be ordered. This required a significant lead time. Rainscreen framing material and fasteners were readily available at common stores. Custom made flashing was required. GBTAC made these on site with the use of a Break. If GBTAC did not have this tool, this material would need to be custom ordered. 	<ul style="list-style-type: none"> WRB was the air control layer, so ensuring continuous membrane behind flashings and penetrations increased the difficulty of installing the WRB. Ensuring the screws that hold on the rainscreen strapping properly embed in a structural member of the wall. Ensuring proper flashing installation and detailing around the window. Custom exterior window trim detail was required. Order of operations for the framer. WRB membrane was required to transfer into the interior at the roof so as to transfer the air control layer to the underside of the roof ceiling. 	2.5 <ul style="list-style-type: none"> Relatively simple to construct. Exterior insulation is the major change from the baseline that makes it more difficult
Double Stud Net Zero	<ul style="list-style-type: none"> All materials used in this assembly were readily available at common hardware/material supply stores aside from the VB. VB and tapes was not readily available and needed to be ordered in. This required a small lead time. 	<ul style="list-style-type: none"> Double walls could be heavy and difficult to move around. Custom window jambs are required to be made to cover the large window rough opening to the interior of the window. Order of operation for the framer. VB needs to be wrapped under the plates of the walls before the walls are installed. Proper installation of the 3 layers of insulation in the cavity to ensure there is no settlement. 	2 <ul style="list-style-type: none"> Simple Construction . Not to dissimilar to the baseline with adding a second wall and extra insulation increasing the difficulty.
Exterior Foam Net Zero	<ul style="list-style-type: none"> Framing material readily available at common hardware/material supply stores. WRB was not readily available and needed to be ordered in. This required a small lead time. XPS and fasteners were readily available at some material supply stores, but had the possibility to need to be ordered in with a small lead time. Custom flashing needed to be made. This was made onsite with a break, otherwise this would have been needed to be ordered from a supplier. 	<ul style="list-style-type: none"> WRB was the air control layer, so ensuring continuous membrane behind flashings and penetrations increased the difficulty of installing the WRB. Ensuring the screws that hold on the rainscreen strapping properly embed in a structural member of the wall. Ensuring proper flashing installation and detailing around the window. Custom exterior window trim detail was required. Installing through flashing in the correct spot at the wall proved difficult. Peel and stick membrane required at least 2 workers to install as it was difficult to remove the backing without adhering the membrane to itself. 	5 <ul style="list-style-type: none"> Most difficult to construct. Long screws and the amount of exterior insulation made this assembly difficult to construct.
Fire Resistant Retrofit	<ul style="list-style-type: none"> ProClima WRB and tapes wer not readily available and needed to be ordered in. This required a small lead time. Exterior mineral wool insulation was not readily available and needed to be ordered. This required a significant lead time. Rainscreen framing material and fasteners were readily available at common stores. Custom made flashing was required. GBTAC made these on site with the use of a Break. If GBTAC did not have this tool, this material would need to be custom ordered. Soprema thermal clips had to be ordered in with minimal lead time. 	<ul style="list-style-type: none"> Attaching the rainscreen strapping to the metal thermal clips proved quite difficult at times. 	3 <ul style="list-style-type: none"> Somewhat difficult to construct. If good screws are used that screw into the metal thermal clips well, the construction would be slightly easier.
Larsen Truss Retrofit	<ul style="list-style-type: none"> All framing material and the WRB material was readily available at common hardware/material supply stores. Dense pack cellulose needed to be installed by a professional installer. Lead time for booking the installer was required. Liquid applied membrane for window bucks was required to be ordered in with a small lead time. 	<ul style="list-style-type: none"> Installing the liquid applied membrane could not be done at a lower temperature. 	2.5 <ul style="list-style-type: none"> Relatively simple to construct. Amount of labour and correct installation of the Larsen Truss raises the difficulty.

• Constructability values are based on the previous experience of the GTAC Staff and conversations with industry



Fire Resistant Retrofit Assembly





