

Larsen Truss Retrofit Assembly

See **Appendix A: Larsen Truss Retrofit Assembly Construction Details** for plans and construction details.

Description & Overview

This assembly was approached the same as the Fire-Resistant Retrofit, as if there was only an exterior retrofit being performed on an existing home from the mid twentieth century. All the structural components were staying as-is and an exterior high-performance retrofit was going to take place. To determine what material to include in the physical mock-up that would represent the existing construction, GBTAC staff previous experience in renovations guided the selection. The existing assembly from exterior to interior contains:

- 3/8 plywood structural sheathing
- 2x4 stud wall with R-12 fibreglass batt insulation
- Polyethylene sheet VB

To determine what the high-performance retrofit additions would include, GBTAC staff utilized information from previously completed retrofit projects, industry feedback, and staff knowledge. The final decision was to display the addition of mineral wool to the exterior of the existing structure with a new airtight WRB and window replacement. The exterior retrofit addition, from exterior to interior contains:

- Exterior cladding
- 1 ½" Rainscreen strapping
- Airtight WRB
- 8" Larsen Truss with dense pack cellulose cavity insulation

The roof and foundation were decided to be the same as with the Fire-Resistant Retrofit Assembly.

The window installed in the mock-up was a representation of a flangeless high-performance European style tilt and turn window with a wooden frame. It is installed in line with where the exterior edge of the existing wall is. The sill of the Larsen truss is sloped so as to drain moisture away, which restricts putting the window farther towards the exterior.

Materials

Materials used for mock-up wall construction are as follows:

- **Rainscreen Strapping**
 - 2x4 SPF lumber
- **Airtight WRB**
 - Membrane – Tytar Building Wrap – mechanically fastened
 - Sealing tape – Siga Wigluv in varying sizes.
 - Sill Pan Flashing and window R.O air sealing – Soprema Sopraseal Liquid Flashing & Soprema Sopraseal Stick Flashpro
- **Larsen Truss**
 - Framing - 2x2 SPF lumber studs spaced 8" apart
 - Structural Gussets – 16" x 8" x ¾" Plywood connecting the interior and exterior Larsen Truss 2x2s. Layout as per designer/engineer specifications
- **Larsen Truss Cavity Insulation**
 - Sopra-Cellulose packed to the required density
- **Existing Structural Wall**
 - 3/8" Plywood structural sheathing
 - 2x4 SPF lumber



- **Cavity Insulation**
 - Owens Corning R-12 Pink Next gen Fiberglass Insulation
- **Vapour Barrier**
 - Existing polyethylene plastic sheeting
- **Assembly Effective Thermal Performance**
 - RSI-6.52 or R-37.03

Construction

The majority of the other assemblies for this project can be somewhat closely compared to each other in terms of construction. This assembly construction was vastly different than any of the others. In terms of difficulty, it was fairly straightforward. GBTAC has seen this assembly, or some other variation of this assembly, used in a majority of deep energy retrofits in the past 2 years in the Calgary area.

Construction of the Larsen Truss consisted of a 2x2 framing member installed at the exterior of the existing structural sheathing, fastened into the structural framing member. 16" x 8" x 3/4" plywood gussets are then fastened to the side of that 2x2 member spaced out as per designed or engineered requirements. A 2x2 framing member is then attached to the exterior edge of the plywood gusset. The result of this is a site made truss. A 3/4" plywood cap was installed along the perimeter of the underside of the truss as well as 3/4" plywood window bucks around the window R.O.'s. The sill buck of the window was sloped downward to allow any moisture to drain away. 2x4 material was used for the rainscreen on this assembly as the bulging of the dense pack cellulose would interfere with the installation of the cladding if only 3/4" material was used.

The air control layer for this assembly was the Typar Building Wrap WRB. Maintaining a continuous air control layer was achieved with this membrane along with the following materials and methods:

- Taping to seal all joints and openings in the WRB.
- Installation of a strip of WRB and tape at the top of the Larsen Truss at the Rafters. Closed Cell spray foam connecting this layer to the ceiling VB.
- Taping electrical wire penetrations.
- Liquid applied membrane of the window bucks. Alternately, an adhered sheet waterproofing membrane can also be utilized in this assembly.
- Taping WRB to mechanical penetrations
- Foam backer rod and caulking to connect the window frame to the liquid applied membrane.

Assembly Advantages

- Wrapping the exterior of the wall assembly with insulation reduces the amount of thermal bridging through the wood structural framing members.
- Retrofitting an existing home saves waste and new construction costs.
- Utilizing the WRB as the air control layer allows for less detailing, and a reduced chance of errors at junctions when the air control layer is to the interior of the assembly.
- Use of a liquid applied membrane to prep and seal the window buck saved a lot of installation time compared to multiple layers of an adhered sheet waterproofing membrane.
- Using a more affordable WRB/Air control membrane resulted in cost savings.
- Most materials were able to be found at a common hardware or building supply store.
- The Larsen Truss can be as thin or thick as needed, allowing for more, or less insulation.



SAIT Green Building Technologies – High Performance Wall Assembly Project

- According to currently available industry Life Cycle Assessment data, cellulose insulation has a lower embodied carbon than the fiberglass, foam, and mineral wool insulation utilized for the other mockups.

Assembly Disadvantages

- Dense pack cellulose requires installation by a certified installer.
- Installing the flangeless window was more difficult for the purposes of this mockup, than the flanged windows for the other assemblies.
- Utilizing a liquid applied membrane required a drying time before the next steps could be completed.
- Not all cladding systems can be accommodated with this exact assembly. For example, if stucco was to be installed, there would need to be a sheathing layer to the exterior of the rainscreen or other accommodations made.
- There may be difficulty finding trades that can or are willing to install this type of assembly in a residential setting.
- Air sealing of the attic poly VB is encouraged to be completed as part of a whole building retrofit, which can be a very difficult and arduous task to complete.

Cost Analysis

The cost analysis revealed that completing a retrofit with this assembly for the model home would cost roughly 7% less compared to constructing the home with the Tier 1 2x6 Assembly.

Of the two retrofit examples, this assembly was the more affordable of the two. Construction to complete this assembly over the other retrofit assembly came out to roughly 14% less overall.

Future Research/Additional Exploration

While GBTAC feels the project shows a good comparison and showcasing of six different assemblies, we have identified areas for future improvements and more accurate comparisons:

- Cost comparisons between the different assemblies when they use all the same materials for the WRB, VB, and sealing tapes.

Appendix A:

Larsen Truss Retrofit Assembly Construction Details


LT¹ RETROFIT ASSEMBLY

EFFECTIVE RSI = 6.52; R-VALUE = 37.03

- EXTERIOR CLADDING
- 1 ½" RAINSCREEN STRAPPING
- AIRTIGHT WATER RESISTANT BARRIER, SHEET APPLIED MEMBRANE, VAPOUR OPEN
- LARSEN TRUSS - 2X2 STUD w/ DENSE PACK CELLULOSE INSULATION¹
- LARSEN TRUSS - 5" DENSE PACK CELLULOSE INSULATION
- LARSEN TRUSS - 2X2 STUD w/ DENSE PACK CELLULOSE INSULATION²
- EXISTING ¾" EXTERIOR SHEATHING
- EXISTING 2X4 STUD w/ BATT FIBREGLASS BATT INSULATION
- EXISTING VAPOUR BARRIER
- EXISTING ½" GYPSUM BOARD
- EXISTING INTERIOR FINISHING

NOTE

1. LT = LARSEN TRUSS
2. 16" X 8" X ¾" PLYWOOD GUSSETS CONNECTING INTERIOR AND EXTERIOR 2 X 2 OF LARSEN TRUSS



ENVELOPE SECTION

1/2" = 1'-0"

LARSEN TRUSS RETROFIT


Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 1/2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.01




1

FOUNDATION TRANSITION SECTION DETAIL

2" = 1'-0"

- | | | |
|--------------------------------------|-------------------------------|-----------------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 13 PLYWOOD GUSSET |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 FIBREGLASS BATT INSULATION | 14 CONCRETE FOUNDATION WALL |
| 3 SELF ADHERED MEMBRANE | | 15 RIM BOARD |
| 4 DENSE PACK CELLULOSE INSULATION | | 16 SUBFLOOR |
| 5 CLADDING | | 17 PARGING |
| 6 FLASHING | | 18 DAMPPROOFING |
| 7 SEALANT | | 19 XPS RIGID INSULATION |
| 8 NON-HARDENING SEALANT | | 20 SOFFIT |
| 9 COMPRESSED FOAM ROD | | 21 J-CHANNEL |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.02

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

RECEPTACLE SECTION DETAIL

4" = 1'-0"

- | | | |
|--------------------------------------|-------------------------------|-------------------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 14 IN USE RECEPTACLE ASSEMBLY |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 PLYWOOD GUSSET | 15 ELECTRICAL WIRE |
| 3 SELF ADHERED MEMBRANE | 13 FIBREGLASS BATT INSULATION | 16 BATTEN |
| 4 DENSE PACK CELLULOSE INSULATION | | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 4" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.03

PREPARED BY SATI GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

WINDOW SILL SECTION DETAIL

4" = 1'-0"

- | | | |
|--------------------------------------|-------------------------------|------------------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 14 GLAZING UNIT |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 PLYWOOD GUSSET | 15 WINDOW SUPPORT SHIM |
| 3 SELF ADHERED MEMBRANE | 13 FIBREGLASS BATT INSULATION | 16 BEVELED SIDING SLOPED DAM |
| 4 DENSE PACK CELLULOSE INSULATION | | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 4" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.04

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

WINDOW JAMB PLAN DETAIL

4" = 1'-0"

- | | | |
|--------------------------------------|-------------------------------|-----------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 14 - 3/4 PLYWOOD BUCK |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 PLYWOOD GUSSET | 15 GLAZING UNIT |
| 3 SELF ADHERED MEMBRANE | 13 FIBREGLOSS BATT INSULATION | |
| 4 DENSE PACK CELLULOSE INSULATION | | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 4" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.05

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.



1

WINDOW HEAD SECTION DETAIL

4" = 1'-0"

- | | | |
|--------------------------------------|-------------------------------|------------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 14 - 3/4" PLYWOOD BUCK |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 PLYWOOD GUSSET | 15 GLAZING UNIT |
| 3 SELF ADHERED MEMBRANE | 13 FIBREGLASS BATT INSULATION | |
| 4 DENSE PACK CELLULOSE INSULATION | | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |

Drawing Title

LARSEN TRUSS RETROFIT


Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 4" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.06




1

FLOOR TO FLOOR TRANSITION SETION DETAIL

2" = 1'-0"

- | | | |
|--------------------------------------|-------------------------|-------------------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 15 FIBREGLASS BATT INSULATION |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 PLYWOOD GUSSET | |
| 3 SELF ADHERED MEMBRANE | 13 RIM BOARD | |
| 4 DENSE PACK CELLULOSE INSULATION | 14 SUBFLOOR | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY


Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.07

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

DUCT OPENING SECTION DETAIL

4" = 1'-0"

- | | | |
|--------------------------------------|-------------------------|-------------------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 15 BATTEN OSB CAP |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 PLYWOOD GUSSET | 16 FIBREGLASS BATT INSULATION |
| 3 SELF ADHERED MEMBRANE | 13 DUCT HOOD | |
| 4 DENSE PACK CELLULOSE INSULATION | 14 DUCT | |
| 5 CLADDING | | |
| 6 FLASHING | | |
| 7 SEALANT | | |
| 8 NON-HARDENING SEALANT | | |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

LARSEN TRUSS RETROFIT

Project Number 2024-009

Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by LL

Checked by BH, NM

Date 2025-04-30


Scale 4" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.08

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.




1

WALL TO ROOF TRANSITION SECTION DETAIL

2" = 1'-0"

- | | | |
|--------------------------------------|-------------------------|----------------------------------|
| 1 VAPOUR BARRIER | 11 RAINSCREEN STRAPPING | 13 ROOFING SHINGLE |
| 2 AIRTIGHT WATER RESISTANT BARRIER | 12 PLYWOOD GUSSET | 14 ROOFING UNDERLAYMENT MEMBRANE |
| 3 SELF ADHERED MEMBRANE | | 15 ROOFING SHEATHING |
| 4 DENSE PACK CELLULOSE INSULATION | | 16 INSULATION STOP |
| 5 CLADDING | | 17 BLOWN INSULATION |
| 6 FLASHING | | 18 J-CHANNEL |
| 7 SEALANT | | 19 SOFFIT |
| 8 NON-HARDENING SEALANT | | 20 FASCIA |
| 9 COMPRESSED FOAM ROD | | |
| 10 EXPANDING POLYURETHANE SPRAY FOAM | | |



1301-16 AVENUE NW CALGARY AB, T2M 0L4

Drawing Title

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.09

PREPARED BY SAT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.
CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.
DO NOT SCALE DRAWING.

LT¹ RETROFIT ASSEMBLY

EFFECTIVE RSI = 6.52; R-VALUE = 37.03


- EXTERIOR CLADDING
- 1 ½" RAINSCREEN STRAPPING
- AIRTIGHT WATER RESISTANT BARRIER, SHEET APPLIED MEMBRANE, VAPOUR OPEN
- LARSEN TRUSS - 2X2 STUD w/ DENSE PACK CELLULOSE INSULATION¹
- LARSEN TRUSS - 5" DENSE PACK CELLULOSE INSULATION
- LARSEN TRUSS - 2X2 STUD w/ DENSE PACK CELLULOSE INSULATION²
- EXISTING ⅜" EXTERIOR SHEATHING
- EXISTING 2X4 STUD w/ BATT FIBREGLASS BATT INSULATION
- EXISTING VAPOUR BARRIER
- EXISTING ½" GYPSUM BOARD
- EXISTING INTERIOR FINISHING

NOTE

1. LT = LARSEN TRUSS
2. 16" X 8" PLYWOOD GUSSETS ACROSS THE TWO 2X2 STUDS

LEGEND

— AIR BARRIER



1

AIR BARRIER CONTINUITY

1/2" = 1'-0"

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 1/2" = 1'-0"


Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.10

LT¹ RETROFIT ASSEMBLY

EFFECTIVE RSI = 6.52; R-VALUE = 37.03



- EXTERIOR CLADDING
- 1 1/2" RAINSCREEN STRAPPING
- AIRTIGHT WATER RESISTANT BARRIER, SHEET APPLIED MEMBRANE, VAPOUR OPEN
- LARSEN TRUSS - 2X2 STUD w/ DENSE PACK CELLULOSE INSULATION¹
- LARSEN TRUSS - 5" DENSE PACK CELLULOSE INSULATION
- LARSEN TRUSS - 2X2 STUD w/ DENSE PACK CELLULOSE INSULATION²
- EXISTING 3/8" EXTERIOR SHEATHING
- EXISTING 2X4 STUD w/ BATT FIBREGLASS BATT INSULATION
- EXISTING VAPOUR BARRIER
- EXISTING 1/2" GYPSUM BOARD
- EXISTING INTERIOR FINISHING

NOTE

1. LT = LARSEN TRUSS
2. 16" X 8" PLYWOOD GUSSETS ACROSS THE TWO 2X2 STUDS

LEGEND

— VAPOUR BARRIER

1 VAPOUR BARRIER CONTINUITY
1/2" = 1'-0"

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 1/2" = 1'-0"


Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.11

LT¹ RETROFIT ASSEMBLY

EFFECTIVE RSI = 7.69; R-VALUE = 44



- EXTERIOR CLADDING
- 1 1/2" RAINSCREEN STRAPPING
- AIRTIGHT WATER RESISTANT BARRIER, SHEET APPLIED MEMBRANE, VAPOUR OPEN
- LARSEN TRUSS - 2X2 STUD w/ DENSE PACK CELLULOSE INSULATION¹
- LARSEN TRUSS - 5" DENSE PACK CELLULOSE INSULATION
- LARSEN TRUSS - 2X2 STUD w/ DENSE PACK CELLULOSE INSULATION²
- EXISTING 3/8" EXTERIOR SHEATHING
- EXISTING 2X4 STUD w/ BATT FIBREGLASS BATT INSULATION
- EXISTING VAPOUR BARRIER
- EXISTING 1/2" GYPSUM BOARD
- EXISTING INTERIOR FINISHING

NOTE

1. LT = LARSEN TRUSS
2. 16" X 8" PLYWOOD GUSSETS ACROSS THE TWO 2X2 STUDS

LEGEND

— WATER BARRIER

1 WATER BARRIER CONTINUITY
1/2" = 1'-0"

LARSEN TRUSS RETROFIT

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by LL Checked by BH, NM Date 2025-04-30 Scale 1/2" = 1'-0"

Project Address N/A

Issued For ALBERTA ECOTRUST FOUNDATION

1.12

Appendix B:

Wall Assembly Effective Thermal Resistance Calculations

Project Name: High-Performance Wall Assembly Project

Project Address:

Assembly Name: Larsen Truss Retrofit Wall Assembly

Materials in Assembly				RSI, (m ² *K)/W	R-Value
Outside Air Film				0.03	0.17
Rainscreen (38mm x 0.0085 RSI/mm)	RSI _F = 0.323	% area of framing = 23	RSI _{Parallel} =	0.20	1.14
Rainscreen Air Cavity (38mm)	RSI _C = 0.18	% area of cavity = 77			
Building Paper				0.00	0.00
Exterior Larsen Truss Framing (38mm x 0.0085 RSI/mm)	RSI _F = 0.323	% area of framing = 23	RSI _{Parallel} =	0.66	3.75
Exterior Larsen Truss Cavity Dense Pack Cellulose (38mm)	RSI _C = 0.95	% area of cavity = 77			
Larsen Truss Cavity Dense Pack Cellulose (127mm)				3.18	18.06
Interior Larsen Truss Framing (38mm x 0.0085 RSI/mm)	RSI _F = 0.323	% area of framing = 23	RSI _{Parallel} =	0.66	3.75
Interior Larsen Truss Cavity Dense Pack Cellulose (38mm)	RSI _C = 0.95	% area of cavity = 77			
OSB Sheathing (9.5mm)				0.0930	0.53
Stud @ 406mm O.C (89mm x 0.0085 RSI/mm)	RSI _F = 0.76	% area of framing = 23	RSI _{Parallel} =	1.50	8.51
Batt Insulation (R12)	RSI _C = 2.11	% area of cavity = 77			
Gypsum (12.7mm)	0.8			0.08	0.45
Interior Air Film	57.6			0.12	0.68
Calculated RSI _{EFF} =				6.52	37.03
9.36 Prescriptive RSI Required =				3.08	17.49
W/HRV				2.97	16.86

Parallel Path Flow Calculations

89mm stud with 89mm Batt Insulation (R12)

RSI_{Parallel}=

100

23

0.76

77

2.11

+




=

1.50


(m²*K)/W

Appendix C:


Cost Analysis Model Home




COLUMN DETAIL
SCALE: 3/8" = 1'-0"



WINDOW TRIM DETAIL
SCALE: 3/16" = 1'-0"




BRACKET DETAIL
SCALE: 3/8" = 1'-0"




FRONT ELEVATION
SCALE: 3/16" = 1'-0"

	ADDRESS:		REVISIONS:	MODEL: 2 STOREY ELEVATION: CRAFTSMAN PAGE 1 OF 10
	TOTAL AREA:	1440 sq.ft.		
	MAIN FLOOR:	700 sq.ft.		
	UPPER FLOOR:	740 sq.ft.		
	GARAGE:	N/A sq.ft.		
	BSMNT DEV:	N/A sq.ft.		
	DECK:	N/A sq.ft.		




ADDRESS: [REDACTED]		
TOTAL AREA:	1440 sq.ft.	REVISIONS:
MAIN FLOOR:	700 sq.ft.	
UPPER FLOOR:	740 sq.ft.	MODEL: 2 STOREY ELEVATION: CRAFTSMAN
GARAGE:	N/A sq.ft.	
BSMNT DEV:	N/A sq.ft.	
DECK:	N/A sq.ft.	PAGE 2 OF 10

LIMITING DISTANCE:	3.08 m
ALLOWABLE OPENINGS:	900 %
EXPOSED BUILDING FACE:	743.33 sq.ft.
UNPROTECTED OPENINGS:	46.84 sq.ft.
ACTUAL OPENINGS:	630%



UNPROTECTED OPENINGS

LIMITING DISTANCE:	122 m
ALLOWABLE OPENINGS:	7.00 %
EXPOSED BUILDING FACE:	139.05 sq.ft.
UNPROTECTED OPENINGS:	21.50 sq.ft.
ACTUAL OPENINGS:	3.12%



RIGHT ELEVATION

SCALE: 3/16" = 1'-0"


ADDRESS:

TOTAL AREA: 1440 sq.ft.
MAIN FLOOR: 700 sq.ft.
UPPER FLOOR: 740 sq.ft.
GARAGE: N/A sq.ft.
BSMNT DEV: N/A sq.ft.
DECK: N/A sq.ft.

REVISIONS:



MODEL: 2 STOREY
ELEVATION:
CRAFTSMAN

PAGE 4 OF 10




FOUNDATION PLAN
SCALE: 3/16" = 1'-0"


STANDARD WALL SCONCE HEIGHT
AT LANDING OR RISERS: 6'-0"

	ADDRESS: 		REVISIONS:	MODEL: 2 STOREY ELEVATION: CRAFTSMAN
	TOTAL AREA:	1440 sq.ft.		
	MAIN FLOOR:	700 sq.ft.		
	UPPER FLOOR:	740 sq.ft.		
	GARAGE:	N/A sq.ft.		PAGE 5 OF 12
	BSMNT DEV:	N/A sq.ft.		
	DECK:	N/A sq.ft.		


NOTE:
MAIN FLOOR WINDOWS
TO BE 7'-11" HIGH UNLESS
OTHERWISE NOTED



MAIN FLOOR PLAN
SCALE: 3/16" = 1'-0"



PASSAGE DETAIL
MAIN
SCALE: 3/16" = 1'-0"




FRIDGE
RECESS DETAIL
SCALE: 3/16" = 1'-0"

NOTE:
DIMENSIONS ARE
TO FINISHED MATERIAL

ADDRESS:		REVISIONS:		MODEL: 2 STOREY ELEVATION: CRAFTSMAN PAGE 6 OF 10
TOTAL AREA:		1440 sq.ft.		
MAIN FLOOR:		700 sq.ft.		
UPPER FLOOR:		740 sq.ft.		
GARAGE:		N/A sq.ft.		
BSMNT DEV:		N/A sq.ft.		
DECK:		N/A sq.ft.		

NOTE:
UPPER FLOOR WINDOWS
TO BE 6'-11" HIGH




UPPER FLOOR PLAN
SCALE: 3/16" = 1'-0"

	ADDRESS: [REDACTED]		
	TOTAL AREA:	1440 sq.ft.	REVISIONS:
	MAIN FLOOR:	700 sq.ft.	
	UPPER FLOOR:	740 sq.ft.	
	GARAGE:	N/A sq.ft.	MODEL: 2 STOREY ELEVATION: CRAFTSMAN
	BSMNT DEV:	N/A sq.ft.	
	DECK:	N/A sq.ft.	PAGE 7 OF 10

NOTE:
MAIN FLOOR WINDOWS TO
BE 7'-11" HIGH UNLESS
OTHERWISE NOTED

UPPER FLOOR WINDOWS
TO BE 6'-11" HIGH UNLESS
OTHERWISE NOTED



CROSS SECTION A
SCALE: 3/16" = 1'-0"

GENERAL NOTES

- GENERAL NOTES:**
- ALL CONSTRUCTION TO CONFORM TO CURRENT A.B.C., FIRE CODES AND 936 PERFORMANCE ENERGY MODEL DETAILS
 - SPECIFICATIONS, CHANGE REQUESTS SHALL OVERRIDE PLANS
 - FINAL GRADING AND SITE CONDITIONS MAY VARY EXTERIOR APPEARANCE
 - SECTION NOTES ARE GENERAL AND MAY VARY OR NOT APPLY TO ALL PLANS
 - ALUMINUM FASCIA AND EAVESTROUGH AS NOTED
 - ALUMINUM VENTED SOFFIT ON FRONT AND REAR ELEVATIONS ONLY.
 - NON-VENTED ALUMINUM SOFFIT ON SIDE ELEVATIONS
 - TRUSS MANUFACTURER TO VERIFY ALL ROOF SLOPES AND TRUSS DESIGN PRIOR TO FABRICATION
- LINTEL NOTES:**
- ALL EXTERIOR LINTELS TO BE 2-2x10 SFF UNLESS NOTED
 - ALL LINTELS OVER 6'-0" MUST HAVE A DOUBLE CRIPPLE
 - INSULATE 4 DRYWALL WALLS WITHIN 4'-0" OF FURNACE 4 HUT
 - INSULATE 4 DRYWALL WALLS ADJACENT TO STAIRS AND LANDING
 - INSULATE AND DRYWALL WALLS AT BASEMENT LAUNDRY WHEN APPLICABLE
 - ANY DISCREPANCIES TO BE REPORTED TO THE DESIGNER PRIOR TO CONSTRUCTION

	ADDRESS:		
	TOTAL AREA: 1440 sq.ft.		REVISIONS:
	MAIN FLOOR: 700 sq.ft.		
	UPPER FLOOR: 740 sq.ft.		
	GARAGE: N/A sq.ft.		
	BSMNT DEV: N/A sq.ft.		
DECK: N/A sq.ft.			
		MODEL: 2 STOREY	
		ELEVATION: CRAFTSMAN	
		PAGE 8 OF 10	

Appendix D:

Wall Assembly Affordability and Constructability Analysis

Cost per sq/ft of Wall Affordability Analysis

Assembly	Cost/sqft of Wall	Notes
Tier 1 2x6	Baseline Cost	Assembly built with materials commonly used in current residential construction. These include; <ul style="list-style-type: none"> • Tyvek WRB. • 6 mil poly vapour barrier.
Exterior Mineral Wool Tier 3	153% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; <ul style="list-style-type: none"> • Siga Majvest WRB (Roughly twice as much per sq/ft coverage of Tyvek). • Siga Majrex vapour barrier (roughly 9x as much per sq/ft coverage of 6 mil poly). • Siga WRB and VB tapes for air sealing. Other Additional Costs: <ul style="list-style-type: none"> • Exterior mineral wool insulation. • Rainscreen material.
Double Stud Net Zero	64% higher than baseline	Incorporates a combination of more commonly used construction materials and high-performance building materials at an additional cost. These include; <ul style="list-style-type: none"> • Typar WRB (similar in price to Tyvek). • Siga Majrex vapour barrier (roughly 9x as much per sq/ft coverage of 6 mil poly). • Siga VB tapes for air sealing. Other Additional Costs: <ul style="list-style-type: none"> • Framing of 2 walls. • Additional insulation to fill wall cavity.
Exterior Foam Net Zero	465% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; <ul style="list-style-type: none"> • Soprema Sopraseal Stick WRB (Roughly 11x as much per sq/ft coverage of Tyvek). • Soprema sill flashing. Other Additional Costs: <ul style="list-style-type: none"> • Exterior XPS insulation. • Rainscreen material. • Fasteners for screwing through a large amount of insulation.
Fire Resistant Retrofit	206% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; <ul style="list-style-type: none"> • ProClima Mento WRB (Roughly 3x as much per sq/ft coverage of Tyvek). • ProClima tapes for air sealing. Other Additional Costs: <ul style="list-style-type: none"> • Exterior mineral wool insulation. • Rainscreen material. • Thermal Clips.
Larsen Truss Retrofit	165% higher than baseline	Incorporates common building materials similar to the baseline home; <ul style="list-style-type: none"> • Typar WRB (similar cost as Tyvek). Additional Costs: <ul style="list-style-type: none"> • Framing material for the Larsen Truss. • Rainscreen material. • WRB tape for air sealing. • Insulation for Larsen Truss cavity. • Soprema liquid applied membrane for window bucks and air sealing.

- No monetary value has been noted as there are many variables that could impact the comparability of these costs.
- This chart is a direct comparison of the cost of the material to construct **ONLY** the wall assembly of the model home.
- This chart only compares the materials selected for each physical mock-up. It cannot be considered a 1 to 1 comparison as different materials selected have different costs, possibly resulting in inflated prices for certain assemblies.

Constructability Analysis

Assembly	Material Availability	Difficulties/Issues	Constructability Rating (1-5)
Tier 1 2x6	<ul style="list-style-type: none"> All material used was available at common hardware/construction material supply stores. Material was all readily available as this is a commonly built assembly across Alberta. 	<ul style="list-style-type: none"> Accoustical sealant can be messy and inconsistent. 	1 Baseline <ul style="list-style-type: none"> Easiest to construct.
Exterior Mineral Wool Tier 3	<ul style="list-style-type: none"> Framing and cavity insulation materials were readily available at common hardware/material supply stores. SIGA WRB, VB and tapes was not readily available and needed to be ordered in. This required a small lead time. Exterior mineral wool insulation was not readily available and needed to be ordered. This required a significant lead time. Rainscreen framing material and fasteners were readily available at common stores. Custom made flashing was required. GBTAC made these on site with the use of a Break. If GBTAC did not have this tool, this material would need to be custom ordered. 	<ul style="list-style-type: none"> WRB was the air control layer, so ensuring continuous membrane behind flashings and penetrations increased the difficulty of installing the WRB. Ensuring the screws that hold on the rainscreen strapping properly embed in a structural member of the wall. Ensuring proper flashing installation and detailing around the window. Custom exterior window trim detail was required. Order of operations for the framer. WRB membrane was required to transfer into the interior at the roof so as to transfer the air control layer to the underside of the roof ceiling. 	2.5 <ul style="list-style-type: none"> Relatively simple to construct. Exterior insulation is the major change from the baseline that makes it more difficult
Double Stud Net Zero	<ul style="list-style-type: none"> All materials used in this assembly were readily available at common hardware/material supply stores aside from the VB. VB and tapes was not readily available and needed to be ordered in. This required a small lead time. 	<ul style="list-style-type: none"> Double walls could be heavy and difficult to move around. Custom window jambs are required to be made to cover the large window rough opening to the interior of the window. Order of operation for the framer. VB needs to be wrapped under the plates of the walls before the walls are installed. Proper installation of the 3 layers of insulation in the cavity to ensure there is no settlement. 	2 <ul style="list-style-type: none"> Simple Construction . Not to dissimilar to the baseline with adding a second wall and extra insulation increasing the difficulty.
Exterior Foam Net Zero	<ul style="list-style-type: none"> Framing material readily available at common hardware/material supply stores. WRB was not readily available and needed to be ordered in. This required a small lead time. XPS and fasteners were readily available at some material supply stores, but had the possibility to need to be ordered in with a small lead time. Custom flashing needed to be made. This was made onsite with a break, otherwise this would have been needed to be ordered from a supplier. 	<ul style="list-style-type: none"> WRB was the air control layer, so ensuring continuous membrane behind flashings and penetrations increased the difficulty of installing the WRB. Ensuring the screws that hold on the rainscreen strapping properly embed in a structural member of the wall. Ensuring proper flashing installation and detailing around the window. Custom exterior window trim detail was required. Installing through flashing in the correct spot at the wall proved difficult. Peel and stick membrane required at least 2 workers to install as it was difficult to remove the backing without adhering the membrane to itself. 	5 <ul style="list-style-type: none"> Most difficult to construct. Long screws and the amount of exterior insulation made this assembly difficult to construct.
Fire Resistant Retrofit	<ul style="list-style-type: none"> ProClima WRB and tapes wer not readily available and needed to be ordered in. This required a small lead time. Exterior mineral wool insulation was not readily available and needed to be ordered. This required a significant lead time. Rainscreen framing material and fasteners were readily available at common stores. Custom made flashing was required. GBTAC made these on site with the use of a Break. If GBTAC did not have this tool, this material would need to be custom ordered. Soprema thermal clips had to be ordered in with minimal lead time. 	<ul style="list-style-type: none"> Attaching the rainscreen strapping to the metal thermal clips proved quite difficult at times. 	3 <ul style="list-style-type: none"> Somewhat difficult to construct. If good screws are used that screw into the metal thermal clips well, the construction would be slightly easier.
Larsen Truss Retrofit	<ul style="list-style-type: none"> All framing material and the WRB material was readily available at common hardware/material supply stores. Dense pack cellulose needed to be installed by a professional installer. Lead time for booking the installer was required. Liquid applied membrane for window bucks was required to be ordered in with a small lead time. 	<ul style="list-style-type: none"> Installing the liquid applied membrane could not be done at a lower temperature. 	2.5 <ul style="list-style-type: none"> Relatively simple to construct. Amount of labour and correct installation of the Larsen Truss raises the difficulty.

• Constructability values are based on the previous experience of the GTAC Staff and conversations with industry



Larsen Truss Retrofit Assembly

















Caution
Do NOT climb or stand on the Wall
displays
Beware of SHARP edges and Splinters
These are real examples of walls and
have all the pointy bits associated
Thank you
enbiv.com



LARGE
TRUSS

Caution
Do NOT climb or stand on the Wall
displays

Beware of SHARP Edges and Splinters
These are real examples of walls and
have all the pointy bits associated

Thank you

enbix.com



FOR RENT
RENTAL









