### Exterior Mineral Wool Tier 3 Assembly

See Appendix A - Exterior Mineral Wool Tier 3 Assembly Construction Details for plans and construction details

#### Description & Overview

The design of this assembly is similar to the Tier 1 2x6 assembly with 2" of mineral wool insulation wrapping the exterior of the 2x6 framing and floor assembly, from the foundation up to the underside of the top chord of the roof trusses. The wall assembly, from exterior to interior, contains:

- Exterior Cladding
- ¾" rainscreen strapping
- 2" mineral wool insulation
  - Connected with ¾" rainscreen strapping and screws as per manufacturers specifications
- Airtight WRB, vapour open
- Structural sheathing
- 2x6 stud wall with fibreglass batt cavity insulation
- Variable vapour barrier
- ½" gypsum board
- Interior finish

The roof and foundation for drafting and mock-up detailing were the same as the Tier 1 2x6 Assembly.

The window installed in the mock-up was the same as the Tier 1 2x6 Assembly. There were several options considered as to where the window would be located within the wall assembly. The placement of the window selected for this project was to install it in a similar way as the Tier 1 2x6 assembly. With the window installed with the flange mounted to the exterior face of the structural sheathing, it allowed for the exterior insulation to cover the nailing flanges, reducing thermal bridging. The other installation method considered was to install the window at the exterior face of the rainscreen. This would have required a custom structural buck to be build to extend the framing R.O. to the outer face of the wall and would have complicated the water control layer detailing at the window. Installing the window to the exterior of the rainscreen would have allowed for the siding to stop right at the window frame and not require a custom cladding return to the inset window when installed at the sheathing layer.

The decision to select this assembly was primarily influenced by researching common methods utilized by residential builders in Alberta to achieve tier 3 standards.

#### Materials

Materials used for mock-up wall construction are as follows:

#### Rainscreen Strapping

- o 1x4 SPF lumber
- Fasteners #10 5" Construction Screws spaced per insulation manufacturers guidelines
- o Bug screen

#### • 2" Mineral wool

o Owens Corning Thermafiber Insulation – R 4.1/Inch

#### Airtight WRB

- o Membrane Siga Majvest 200 Mechanically fastened
- Sealing tape Siga Wigluv in varying sizes.
- Sill Pan Flashing Siga Wigluv

#### Structural Wall

- o 3/8" OSB structural sheathing
- o 2x6 SPF lumber

#### Cavity Insulation

Owens Corning R-22 Pink Next gen Fiberglass Insulation

#### Vapour Barrier

- Siga Majrex
- Sealing Tape Siga Fentrim

#### Assembly Effective Thermal Performance

o RSI-4.58 or R-26.01

#### Construction

This assembly was very similar to the Tier 1 2x6 Assembly as far as structural framing was concerned. The air control layer for this assembly was the Siga Majvest 200 WRB. Maintaining a continuous air control layer was achieved with this membrane along with the following materials and methods:

- Taping to seal all joints and openings in the WRB.
- Installation of a strip of WRB between the top and cap plate of the wall at the truss connection, draping to the exterior and interior. Taping the joints to the WRB and VB.
- Taping electrical wire penetrations.
- Taping WRB to window frame on the sides and the top.
- Taping WRB to mechanical penetrations
- Foam backer rod and caulking to connect the window frame sill to the WRB at the sill.

Sealing the WRB to maintain airtightness was much easier than sealing the interior VB as there were fewer junctions and penetrations to detail. Additionally, being installed on the sheathing provided solid material for taping and rolling the tape joints to seal the WRB at all laps and penetrations.

The largest difference between this assembly and the Tier 1 Assembly is the installation of 2" of mineral wool and a rainscreen to the exterior of the WRB. The mineral wool was installed by initially tacking it in place with plastic cap nails. The 3/4" rainscreen strapping was then installed at the same spacing as the structural framing, ensuring the fasteners attaching the strapping were imbedded into a structural member.

Custom made flashing was required for the areas that the flashing had to return all the way to the back side of the WRB. A bug screen was installed at the top and base of rainscreen sections in between the strapping to prevent bugs and small animals from entering the

assembly. A custom engineered wood window trim return was made for the exterior trim of the window.

#### **Assembly Advantages**

- Wrapping the exterior of the wall assembly in 2" of mineral wool insulation reduces the amount of thermal bridging through the wood structural framing members
- The mineral wool insulation used for the mockup was moisture resistant. This allowed it to be installed as part of the WRB.
- The mineral wool insulation used for the mockup has fire resistant qualities.
- The structural framing is very similar to how most homes are currently being built (Tier 1 2x6 Assembly).
- Utilizing the WRB as the air control layer allowed for less challenging detailing, and a reduced chance of errors at junctions and penetrations compared to locating the air control layer to the interior of the assembly.
- Attaching the mineral wool with ¾" strapping material created a rainscreen for the assembly which would assist with moisture management.
- The framing and construction method for this assembly does not differ greatly from the Tier 1 2x6 assembly.
- Adding only 2" of exterior insulation allowed for the use of screws that can be found at most hardware or building supply stores.

#### Assembly Disadvantages

- High-performance membranes and materials were costly, and needed to be ordered from the manufacturer.
- Not all cladding systems can be accommodated with this exact assembly. For example, if stucco was to be installed, there would need to be a sheathing layer to the exterior of the rainscreen or other accommodations made.
- Overdriving rainscreen strapping screws can compress the mineral wool insulation, creating a wavy exterior finish.
- Considerable forethought, planning and organization is required, as mistakes
  can be more time consuming and difficult to fix than the Tier 1 2x6 Assembly.

#### Cost Analysis

Upon completing a cost analysis of this assembly compared to the Tier 1 2x6 Assembly, the cost to construct this assembly for the model home came out to roughly 54% more.

GBTAC found that the largest cause of additional costs was due to the use of the high-quality membranes and tapes, followed by the mineral wool insulation.



## Appendix A:

Exterior Mineral Wool Tier 3 Assembly **Construction Details** 

## EXT. MINERAL WOOL T3 1.09 WALL ASSEMBLY EFFECTIVE RSI = 4.58; R-VALUE = 26.01 EXTERIOR CLADDING • ¾" RAINSCREEN STRAPPING • 2" MINERAL WOOL INSULATION -C/W STRAPPING & SCREWS AS PER SPEC. • AIRTIGHT WATER RESISTANT BARRIER, SHEET APPLIED MEMBRANE, VAPOUR OPEN 1.08 • 3/8" EXTERIOR SHEATHING • 2X6 STUD WALL WITH FIBERGLASS BATT CAVITY INSULATION • VARIABLE VAPOUR BARRIER • ½" GYPSUM BOARD • INTERIOR FINISH 1 1.07 **NOTES** 1.06 EXT.= EXTERIOR T3= TIER 3 1.05 1.04 1.03 1 1.02 **ENVELOPE SECTION** 1/2" = 1'-0" EXT. MINERAL WOOL T3 WALL



PRESENDED IT SATE GETAC.

THIS GRAWING IS THE PROPERTY OF THE SOLITHERN ALBERTA INSTITUTE OF TECHNICLOGY GETAC OFFICE AND MANOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WENTEN CONSENT.

CONTRACTIONS SHALL WERFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCES PRIOR TO CONSTRUCTION.


DO NOT SCALE PROPRING.

 Project Number
 2024-009
 Project Name
 HIGH PERFORMANCE WALL ASSEMBLY

 Drawn by
 PY
 Checked by
 BH, NM
 Date
 2025-04-30
 Scale
 1/2" = 1'-0"

 Project Address
 N/A

Issued For ALBERTA ECOTRUST FOUNDATION



FOUNDATION TRANSITION SECTION DETAIL

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT **BARRIER** 

3 SELF ADHERED MEMBRANE

**4 FIBREGLASS BATT INSULATION** 

5 CLADDING

6 FLASHING

7 SEALANT

**8 NON-HARDENING SEALANT** 

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM

11 2" MINERAL WOOL INSULATION 13 CAST-IN-PLACE CONCRETE

12 RAINSCREEN STRAPPING

14 RIM BOARD

2" = 1'-0"

15 SUBFLOOR

16 PARGING

17 DAMPPROOFING


**18 SPRAY FOAM INSULATION** 

# 1301-16 AVENUE NW CALGARY AB, T2M 0L4

## EXT. MINERAL WOOL T3 WALL

ALBERTA ECOTRUST FOUNDATION

Project Number Project Name HIGH PERFORMANCE WALL ASSEMBLY Checked by BH, NM 2025-04-30 2" = 1'- 0"



1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT **BARRIER** 

- 3 SELF ADHERED MEMBRANE
- **4 FIBREGLASS BATT INSULATION**
- 5 CLADDING
- 6 FLASHING
- 7 SEALANT
- **8 NON-HARDENING SEALANT**
- 9 COMPRESSED FOAM ROD
- 10 EXPANDING POLYURETHANE SPRAY FOAM

11 2" MINERAL WOOL INSULATION 13 IN USE RECEPTACLE ASSEMBLY 12 RAINSCREEN STRAPPING

14 ELECTRICAL WIRE


15 BATTEN



## EXT. MINERAL WOOL T3 WALL

Project Number Project Name HIGH PERFORMANCE WALL ASSEMBLY Date 2025-04-30 Checked BH, NM 4" = 1'- 0"

ALBERTA ECOTRUST FOUNDATION



1

## WINDOW SILL SECTION DETAIL

4" = 1'-0"

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT 12 RAINSCREEN STRAPPING **BARRIER** 

- 3 SELF ADHERED MEMBRANE
- **4 FIBREGLASS BATT INSULATION**
- 5 CLADDING
- 6 FLASHING
- 7 SEALANT
- **8 NON-HARDENING SEALANT**
- 9 COMPRESSED FOAM ROD
- 10 EXPANDING POLYURETHANE SPRAY FOAM

11 2" MINERAL WOOL INSULATION 13 GLAZING UNIT

14 WINDOW SUPPORT SHIM


15 BEVELED SIDING SLOPED DAM



## EXT. MINERAL WOOL T3 WALL

Project Number Project Name HIGH PERFORMANCE WALL ASSEMBLY Date 2025-04-30 Checked by BH,NM 4" = 1'- 0"

ALBERTA ECOTRUST FOUNDATION



## WINDOW JAMB PLAN DETAIL

4" = 1'-0"

12 RAINSCREEN STRAPPING

11 2" MINERAL WOOL INSULATION 13 GLAZING UNIT

14 CLOSURE FLASHING

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT

**BARRIER** 


- 3 SELF ADHERED MEMBRANE
- **4 FIBREGLASS BATT INSULATION**
- 5 CLADDING
- 6 FLASHING
- 7 SEALANT
- **8 NON-HARDENING SEALANT**
- 9 COMPRESSED FOAM ROD
- 10 EXPANDING POLYURETHANE SPRAY FOAM

1301-16 AVENUE NW CALGARY AB, T2M 0L4

## EXT. MINERAL WOOL T3 WALL

Project Number  $^{
m Project\,Name}$  HIGH PERFORMANCE WALL ASSEMBLY Checked by BH, NM 2025-04-30 4" = 1'- 0"

ALBERTA ECOTRUST FOUNDATION





## WINDOW HEAD SECTION DETAIL

4" = 1'-0"

11 2" MINERAL WOOL INSULATION 13 GLAZING UNIT

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT 12 RAINSCREEN STRAPPING **BARRIER** 

3 SELF ADHERED MEMBRANE

**4 FIBREGLASS BATT INSULATION** 

5 CLADDING


6 FLASHING

7 SEALANT

**8 NON-HARDENING SEALANT** 

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM




PREPARED BY SAIT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MAY
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.

## EXT. MINERAL WOOL T3 WALL

Project Number Project Name HIGH PERFORMANCE WALL ASSEMBLY Date 2025-04-30 Checked BH, NM 4" = 1'- 0"

ALBERTA ECOTRUST FOUNDATION



FLOOR TO FLOOR TRANŠITION SECTION DETAIL

12 RAINSCREEN STRAPPING

11 2" MINERAL WOOL INSULATION 13 RIM BOARD

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT

**BARRIER** 

3 SELF ADHERED MEMBRANE

**4 FIBREGLASS BATT INSULATION** 

**5 CLADDING** 

6 FLASHING

7 SEALANT

**8 NON-HARDENING SEALANT** 

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM

## EXT. MINERAL WOOL T3 WALL

 Project Number
 2024-009
 Project Name
 HIGH PERFORMANCE WALL ASSEMBLY

 Drawn by
 PY
 Checked by
 BH, NM
 Date 2025-04-30
 Scale 2" = 1'- 0"

 Project Address N/A
 N/A
 Project Address Project A

ALBERTA ECOTRUST FOUNDATION

1.07

2" = 1'-0"

15 SPRAY FOAM INSULATION


14 SUBFLOOR

1301-16 AVENUE NW CALGARY AB, T2M 014

PREPARED BY SAIT GETAL.

THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GETAC OFFICE AND MA
OTO BE REPRODUCED OR DISTRIBUTE OWN WHICH THE AUTHORS WRITTEN CONSENT.

CONTRACTORS SHALL VERIFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.



## **DUCT OPENING SECTION DETAIL**

4" = 1'-0"

12 RAINSCREEN STRAPPING

11 2" MINERAL WOOL INSULATION 13 DUCT HOOD

14 DUCT

15 BATTEN

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT

**BARRIER** 

3 SELF ADHERED MEMBRANE

**4 FIBREGLASS BATT INSULATION** 

**5 CLADDING** 

6 FLASHING

7 SEALANT

**8 NON-HARDENING SEALANT** 

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM

1301-16 AVENUE NW CALGARY AB, T2M 0L4

PREPAIRED BY SAFE BETA.

THE ROWSHIP OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC OFFICE AND MY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WINTEN CONSENT.

CONTRACTORS SHALL VERFY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCES PRIOR TO CONSTRUCTION.
DO NOT SCALE DENAINING.


## EXT. MINERAL WOOL T3 WALL

Project Number 2024-009 Project Name HIGH PERFORMANCE WALL ASSEMBLY

Drawn by PY Checked by BH, NM Date 2025-04-30 Scale 4" = 1'- 0"

Project Address N/A

ALBERTA ECOTRUST FOUNDATION



2" = 1'-0"

1 VAPOUR BARRIER

2 AIRTIGHT WATER RESISTANT **BARRIER** 

3 SELF ADHERED MEMBRANE

**4 FIBREGLASS BATT INSULATION** 

5 CLADDING

6 FLASHING

7 SEALANT

**8 NON-HARDENING SEALANT** 

9 COMPRESSED FOAM ROD

10 EXPANDING POLYURETHANE SPRAY FOAM

11 2" MINERAL WOOL INSULATION

12 RAINSCREEN STRAPPING

13 ROOFING SHINGLE

14 ROOFING UNDERLAYMENT

MEMBRANE

15 ROOFING SHEATHING

**16 INSULATION STOP** 

17 BLOWN INSULATION

18 J-CHANNEL

19 SOFFIT


20 FASCIA

1301-16 AVENUE NW CALGARY AB, T2M 0L4

## EXT. MINERAL WOOL T3 WALL

Project Number Project Name HIGH PERFORMANCE WALL ASSEMBLY Checked BH, NM 2025-04-30 2" = 1'- 0"

ALBERTA ECOTRUST FOUNDATION




PREPARED BY SAIT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GBTAC O
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.

1301-16 AVENUE NW CALGARY AB, T2M 0L4

Checked by BH, NM 2025-04-30 1/2" = 1'- 0" Project Address N/A

ALBERTA ECOTRUST FOUNDATION





PREPARED BY SAIT GRITA:

THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GRITAC OFFICE AND MAY NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.


CONTRACTORS SHALL VERRY ALL DIMENSIONS ON SITE AND REPORT DISCREPANCIES PRIOR TO CONSTRUCTION.

 Project Number
 2024-009
 Project Name
 HIGH PERFORMANCE WALL ASSEMBLY

 Drawn by
 PY
 Checked by
 BH, NM
 Date by
 2025-04-30
 Scale by
 1/2" = 1'- 0"

Project Address N/A

ALBERTA ECOTRUST FOUNDATION





PREPARED BY SAIT GBTAC
THIS DRAWING IS THE PROPERTY OF THE SOUTHERN ALBERTA INSTITUTE OF TECHNOLOGY GB
NOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE AUTHORS WRITTEN CONSENT.

## EXT. MINERAL WOOL T3 WALL

Project Number Project Name HIGH PERFORMANCE WALL ASSEMBLY Checked by BH, NM 2025-04-30 1/2" = 1'- 0" Project Address N/A

ALBERTA ECOTRUST FOUNDATION



# Appendix B:

Wall Assembly Effective Thermal Resistance **Calculations** 

Project Name:

**High-Performance Wall Assembly Project** 

Project Address:

Assembly Name:

## **Exterior Mineral Wool Tier 3 Wall Assembly**

Materials in Assembly					RSI, (m <sup>2</sup> *K)/W	R-Value
Outside Air Film					0.03	0.47
Outside Air Film					0.03	0.17
Rainscreen Framing (20mm x 0.0085 RSI/mm)	RSI <sub>F</sub> =	0.17	% area of framing =	20	RSI <sub>Parallel</sub> =	
Rainscreen Air Cavity (20mm)	RSI <sub>C</sub> =	0.18	% area of cavity =	80	0.18	1.02
Exterior Mineral Wool (51mm)					1.41	8.02
Building Paper					0.00	0.00
OSB Sheathing (9.5mm)					0.0930	0.53
Stud @ 610 (140mm x 0.0085 RSI/mm)	RSI <sub>F</sub> =	1.19	% area of framing =	20	RSI <sub>Parallel</sub> =	
Batt Insulation (R22)	RSI <sub>C</sub> =	3.87	% area of cavity =	80	2.67	15.15
Vapour Barrier					0.00	0.00
Gypsum (12.7mm)		0.8			0.08	0.45
Interior Air Film		57.6			0.12	0.68
			Calculated RSI <sub>E</sub>	<sub>FF</sub> =	4.58	26.01
			9.36 Prescriptive RSI R	equired =	3.08	17.49
			W/HRV		2.97	16.86

## Parallel Path Flow Calculations


140mm stud with Batt Insulation (R22)


$$RSI_{Parallel} = \frac{100}{\frac{20}{1.19} + \frac{80}{3.87}} = 2.67 \quad (m2*K)/W$$




# Appendix C:


Cost Analysis Model Home









COLUMN DETAIL SCALE: 3/8" = 1'-0"





SCALE: 3/16" = 1'-0"











ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV: DECK:	1440 sq.ft.   REVISIONS: 700 sq.ft.   740 sq.ft.   N/A sq	MODEL: 2 STOREY ELEVATION: GRAFTSMAN PAGE 2 OF 10

#### UNPROTECTED OPENINGS

LIMITING DISTANCE:
ALLOWABLE OPENINGS;
EXPOSED BUILDING FACE:
UNPROTECTED OPENINGS;
ACTUAL OPENINGS;


3,08 m 9,00 % 143,33 sq.ft. 46,84 sq.ft. 6,30%




ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV:	1440 sq.ft. 700 sq.ft. 740 sq.ft. N/A sq.ft. N/A sq.ft.	MODEL: 2 STOREY ELEVATION: CRAFTSMAN
DECK:	N/A sq.ft.	PAGE 3 OF 10

#### UNPROTECTED OPENINGS

LIMITING DISTANCE: ALLOWABLE OPENINGS: EXPOSED BUILDING FACE: UNPROTECTED OPENINGS: ACTUAL OPENINGS: 1.22 m T.00 % T39.05 eq.ft. 27.50 eq.ft. 3.72%



ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV:	1440 sq.ft. REVISIONS: 700 sq.ft. 740 sq.ft. N/A sq.ft.	MODEL: 2 STOREY ELEVATION: CRAFTSMAN
DECK:	N/A sq.ft. N/A sq.ft.	PAGE 4 OF 10






STANDARD WALL SCONCE HEIGHT AT LANDING OR RISERS: 6'-8"

ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV:	1440 sq.ft. 700 sq.ft. 740 sq.ft. N/A sq.ft.	MODEL: Z STOREY ELEVATION: CRAFTSMAI
DECK:	N/A sq.ft. N/A sq.ft.	PAGE 5 0

NOTE: MAIN FLOOR WINDOWS TO BE 7'-11" HIGH UNLESS OTHERWISE NOTED 41'-0" 35'-0" 6'-0" 3'-72" 13'-91" 5'-68" 10'-4" -2×6 FULL HEIGHT FURRING WALL 9 16" O.C. 2'-5' 10-4 - 6x6 POST BUILT UP COLUMN, SEE DETAIL ALUMINUM RAILING - 12" DROPPED BULKHEAD FRIDGE RECESS SEE DETAIL TRUSSES OTR MICRO 11 7/8" ENG. FLOOR JOISTS SPACING AS PER SUPPLIER CANT. DINING AREA LIFESTYLE ROOM 9'-9" x 12'-2" 12'-9" x 12'-0" II" FLUSH EATING BAR 3'-31" 4'-61" 5'-9½" 3'-2" 42" HIGH STUBWALL PASSAGE. OPEN TO ABOVE PANTRY 42" POURED CONCRETE WALKWAY 5'-0" PAPER ALUMINUM RAILING ENG. HEADER 40/24 P T/O WINDOW-TO MATCH T/O DOOR/ TRANSOM ENG. WALL, -SEE DETAIL 14" WIDE x 6" DEEP DROPPED BULKHEAD - 60"x40 PRECAST CONCRETE LANDING 11'-10\frac{1}{2}" 1-9" 2'-9" 2'-11" 2'-0" CANT. 5-68" 13'-72" 4'-5" 4'-8" 5'-8" 35'-0" MAIN FLOOR PLAN WIDTH TO VARY SCALE: 3/16" = 1'-0" NOTE: DIMENSIONS ARE TO FINISHED MATERIAL ADDRESS: PASSAGE DETAIL FRIDGE RECESS DETAIL MAIN 1440 sq.ft. REVISIONS: TOTAL AREA: MODEL: 2 STOREY 700 sq.ft. 740 sq.ft. MAIN FLOOR: SCALE: 3/16" = 1'-0" SCALE: 3/16" - 1'-0" ELEVATION:


UPPER FLOOR: GARAGE: N/A sq.ft. CRAFTSMAN BSMNT DEV: DECK: N/A sq.ft. N/A sq.ft. PAGE 6 OF 10 NOTE: UPPER FLOOR WINDOWS TO BE 6'-11" HIGH





ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV:	1440 sq.ft. 700 sq.ft. 740 sq.ft. N/A sq.ft.	MODEL: 2 STOREY ELEVATION: GRAFTSMAN
DECK:	N/A sq.ft. N/A sq.ft.	PAGE 7 OF 10

NOTE: MAIN FLOOR WINDOWS TO BE T'-11" HIGH UNLESS UPPER FLOOR WINDOWS TO BE 6'-11" HIGH UNLESS OTHERWISE NOTED



- ENERGY FIODEL DETAILS
  -SPECIFICATIONS, CHANGE REQUESTS SHALL OVERRIDE PLANS
  -FINAL GRADING AND SITE CONDITIONS MAY VARY EXTERIOR APPEARANCE
  -SECTION NOTES ARE GENERAL AND MAY VARY OR NOT APPLY TO ALL PLANS

- -ALUMINUM FASCIA AND EAVESTROUGH AS NOTED
  -ALUMINUM VENTED SOFFIT ON FRONT AND REAR ELEVATIONS ONLY.
  -NON-VENTED ALUMINUM SOFFIT ON SIDE ELEVATIONS
  -TRUSS MANUFACTURER TO VERIFY ALL ROOF SLOPES AND TRUSS DESIGN PRIOR TO FABRICATION

- -TRUSS MANUFACTURER TO VERIFY ALL ROOF SLOPES AND TRUSS DESIGN PRIOR TO FALINTEL NOTES:
  -ALL EXTERIOR LINTELS TO BE 2-2×IØ SPF UNLESS NOTED
  -ALL LINTELS OVER 6'-Ø" MUST HAVE A DOUBLE CRIPPLE
  -INSULATE 4 DRYWALL WALLS WITHIN 4'Ø" OF FURNACE 4 HUT
  -INSULATE 4 DRYWALL WALLS ADJACENT TO STAIRS AND LANDING
  -INSULATE AND DRYWALL WALLS AT BASEMENT LAUNDRY WHEN APPLICABLE
  -ANY DISCREPANCIES TO BE REPORTED TO THE DESIGNER PRIOR TO CONSTRUCTION

ADDRESS:		
TOTAL AREA: MAIN FLOOR: UPPER FLOOR: GARAGE: BSMNT DEV: DECK:	700 sq.rt.	MODEL: 2 STOREY ELEVATION: CRAFTSMAN PAGE 8 OF 10



# Appendix D:

Wall Assembly Affordability and Constructability Analysis

Cost per sq/ft of Wall Affordability Analysis				
Assembly	Cost/sqft of Wall	Notes		
Tier 1 2x6	Baseline Cost	Assembly built with materials commonly used in current residential construction. These include;  • Tyvek WRB.  • 6 mil poly vapour barrier.		
Exterior Mineral Wool Tier 3	<b>153%</b> higher than baseline	Incorporates high-performance building materials at an additional cost. These include;  • Siga Majvest WRB (Roughly twice as much per sq/ft coverage of Tyvek).  • Siga Majrex vapour barrier (roughly 9x as much per sq/ft coverage of 6 mil poly).  • Siga WRB and VB tapes for air sealing.  Other Additional Costs:  • Exterior mineral wool insulation.  • Rainscreen material.		
Double Stud Net Zero	<b>64%</b> higher than baseline	Incorporates a combination of more commonly used construction materials and high-performance building materials at an additional cost. These include;  • Typar WRB (similar in price to Tyvek).  • Siga Majrex vapour barrier (roughly 9x as much per sq/ft coverage of 6 mil poly).  • Siga VB tapes for air sealing.  Other Additional Costs:  • Framing of 2 walls.  • Additional insulation to fill wall cavity.		
Exterior Foam Net Zero	<b>465%</b> higher than baseline	Incorpotates high-performance building materials at an additional cost. These include;  • Soprema Sopraseal Stick WRB (Roughly 11x as much per sq/ft coverage of Tyvek).  •Soprema sill flashing.  Other Additional Costs:  • Exterior XPS insulation.  • Rainscreen material.  • Fasteners for screwing through a large amount of insulation.		
Fire Resistant Retrofit	206% higher than baseline	Incorporates high-performance building materials at an additional cost. These include; • ProClima Mento WRB (Roughly 3x as much per sq/ft coverage of Tyvek. • ProClima tapes for air sealing.  Other Additional Costs: • Exterior mineral wool insulation. • Rainscreen material. • Thermal Clips.		
Larsen Truss Retrofit	165% higher than baseline	Incorporates common building materials similar to the baseline home;  • Typar WRB (similar cost as Tyvek).  Additional Costs:  • Framing material for the Larsen Truss.  • Rainscreen material.  • WRB tape for air sealing.  • Insulation for Larsen Truss cavity.  • Soprema liquid applied membrane for window bucks and air sealing.		

- No monetary value has been noted as there are many variables that could impact the comparability of these costs.
- This chart is a direct comparison of the cost of the material to construct **ONLY** the wall assembly of the model home.
- This chart only compares the materials selected for each physical mock-up. It cannot be considered a 1 to 1 comparison as different
  materials selected have different costs, possibly resulting in inflated prices for certain assemblies.

Constructability Analysis					
Assembly	Material Availability	Difficulties/Issues	Constructability Rating (1-5)		
Tier 1 2x6	All material used was available at common hardware/construction material supply stores.     Material was all readily available as this is a commonly built assembly across Alberta.	Accoustical sealant can be messy and inconsistent.	1 Baseline •Easiest to construct.		
Exterior Mineral Wool Tier 3	Framing and cavity insulation materials were readily available at common hardware/material supply stores.     SIGA WRB, VB and tapes was not readily available and needed to be ordered in. This required a small lead time.     Exterior mineral wool insulation was not readily available and needed to be ordered. This required a significant lead time.     Rainscreen framing material and fasteners were readily available at common stores.     Custom made flashing was required. GBTAC made these on site with the use of a Break. If GBTAC did not have this tool, this material would need to be custom ordered.	strapping properly embed in a structural member of the wall.  • Ensuring proper flashing installation and detailing around the window.  • Custom exterior window trim detail was required.	Relatively simple to construct.     Exterior insulation is the major change from the baseline that makes it more difficult		
Double Stud Net Zero	VB and tapes was not readily available and needed to be ordered in. This required a small lead time.	be wrapped under the plates of the walls before the walls are installed.	2 • Simple Construction . • Not to dissimilar to the baseline with adding a second wall and extra insulation increasing the difficulty.		
Exterior Foam Net Zero	Framing material readily available at common hardware/material supply stores.     WRB was not readily available and needed to be ordered in. This required a small lead time.     XPS and fasteners were readily available at some material supply stores, but had the possibility to need to be ordered in with a small lead time.     Custom flashing needed to be made. This was made onsite with a break, otherwise this would have been needed to be ordered from a supplier.	WRB was the air control layer, so ensuring continuous membrane behind flashings and penetrations increased the difficulty of installing the WRB. Ensuring the screws that hold on the rainscreen strapping properly embed in a structural member of the wall. Ensuring proper flashing installation and detailing around the window. Custom exterior window trim detail was required. Installing through flashing in the correct spot at the wall proved difficult. Peel and stick membrane required at least 2 workers to install as it was difficult to remove the backing without adhering the membrane to itself.	• Most difficult to construct. • Long screws and the amount of exterior insulation made this assembly difficult to construct.		
Fire Resistant Retrofit	ProClima WRB and tapes wer not readily available and needed to be ordered in. This required a small lead time.  Exterior mineral wool insulation was not readily available and needed to be ordered. This required a significant lead time.  Rainscreen framing material and fasteners were readily available at common stores.  Custom made flashing was required. GBTAC made these on site with the use of a Break. If GBTAC did not have this tool, this material would need to be custom ordered.  Soprema thermal clips had to be ordered in with minimal lead time.	Attaching the rainscreen strapping to the metal thermal clips proved quite difficult at times.	• Somewhat difficult to construct. • If good screws are used that screw into the metal thermal clips well, the construction would be slightly easier.		
Larsen Truss Retrofit	All framing material and the WRB material was readily available at common hardware/material supply stores. Dense pack cellulose needed to be installed by a professional installer. Lead time for booking the installer was required. Liquid applied membrane for window bucks was required to be ordered in with a small lead time.	Installing the liquid applied membrane could not be done at a lower temperature.	2.5 Relatively simple to construct. Amount of labour and correct installation of the Larsen Truss raises the difficulty.		

## Exterior Mineral Wool Tier 3 Assembly

